

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER THREE RIVERS 32-15-720				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT WILDCAT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR AXIA ENERGY LLC						7. OPERATOR PHONE 720 746-5200				
8. ADDRESS OF OPERATOR 1430 Larimer Ste 400, Denver, CO, 80202						9. OPERATOR E-MAIL rsatre@axiaenergy.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) FEE			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Kay Anderson						14. SURFACE OWNER PHONE (if box 12 = 'fee') 801-224-2907				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') 683 W. 925 S. , Orem, UT 84058						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		660 FSL 890 FWL		SWSW	32	7.0 S	20.0 E	S		
Top of Uppermost Producing Zone		660 FSL 460 FWL		SWSW	32	7.0 S	20.0 E	S		
At Total Depth		660 FSL 460 FWL		SWSW	32	7.0 S	20.0 E	S		
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 460			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 16			26. PROPOSED DEPTH MD: 9070 TVD: 9036				
27. ELEVATION - GROUND LEVEL 4800			28. BOND NUMBER LPM9046682			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 49-2262 - RNI at Green River				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
SURF	11	8.625	0 - 1100	32.0	J-55 LT&C	8.7	Premium Lite High Strength	110	2.97	11.5
							Class G	115	1.16	15.8
PROD	7.875	5.5	0 - 9070	17.0	N-80 LT&C	9.2	Premium Lite High Strength	575	2.31	12.0
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton				TITLE Permitting Agent (Buys & Associates, Inc)				PHONE 435 719-2018		
SIGNATURE				DATE 05/23/2012				EMAIL starpoint@etv.net		
API NUMBER ASSIGNED 43047527360000				APPROVAL Permit Manager						

DRILLING PLAN

Axia Energy, LLC
Three Rivers Project
Three Rivers #32-15-720
SWSW Sec 32 T7S R20E
Uintah County, Utah

1. ESTIMATED FORMATION TOPS

FORMATION	TOP (TVD)	COMMENTS
Uinta	Surface	Gas & Degraded Oil; Possible Brackish H ₂ O
Green River	3,106'	Oil & Associated Gas
Lower Green River*	5,123'	Oil & Associated Gas
Wasatch*	7,036'	Oil & Associated Gas
TD	9,070' (MD)	9,036' (TVD)

NOTE: Datum, Ground Level (GL) Elevation: 4,800'; Asterisks (*) denotes target pay intervals

A) The State of Utah, Division of Oil, Gas and Mining will be notified within 24 hours of spudding the well.

2. CASING PROGRAM

CASING	HOLE SIZE	DEPTH SET (MD)	CSG SIZE	WGHT	GRD	THRD	CAPACITY (bbl/ft)
CONDUCTOR		50-75	13 3/8				
SURFACE	11	1100 ±	8 5/8	32.0	J-55	LTC	0.0609
PRODUCTION	7 7/8	9,070'	5 1/2	17.0	N-80	LTC	0.0232

NOTE: All casing depth intervals are to surface unless otherwise noted.

Casing Specs

SIZE (in)	ID (in)	DRIFT DIA (in)	COLLAPSE RESISTANCE (psi)	INTERNAL YIELD (psi)	TENSILE YIELD (lbs)	JOINT STRENGTH (lbs)
8 5/8	7.921	7.796	2,530	3,930	503,000	417,000
5 1/2	4.892	4.767	6,280	7,740	397,000	348,000

*The State of Utah will be notified 24 hours prior to running casing, cementing, and BOPE testing

FLOAT EQUIPMENT

SURFACE (8 5/8):

Float Shoe, 1 JNT Casing, Float Collar

Centralizers: 1st 4 Joints: every joint
Remainder: every third joint

PRODUCTION (5 1/2):

Float Shoe, 1 JNT Casing, Float Collar

Centralizers: 1st 4 Joints: every joint
Remainder: every third joint 500' into surface casing

NOTE: 5 1/2" 17# N-80 or equivalent marker collar or casing joints will be placed at the top of the Green River and approximately 400' above the Wasatch.

3. CEMENT PROGRAM

CONDUCTOR (13 3/8):

Ready Mix – Cement to surface

SURFACE (8 5/8):

Cement Top: Surface

Lead: 110 sks, Premium Lightweight Cmt w/ additives, 11.50 ppg, 2.97 cf/sk, 50% excess

Tail: 115 sks Class G Cement w/ additives, 15.80 ppg, 1.16 cf/sk, 50% excess

NOTE: The above volumes are based on a gauge-hole + 50% excess.

PRODUCTION (5 1/2):

Cement Top – 2,700'

575 sacks – Light Premium Cement w/ additives – 12.0 ppg, 2.31 ft³/sk – 20% excess

NOTE: The above volumes are based on gauge hole + 20% excess. Adjustments will be made and volumes will be caliper + 10%.

NOTE: The above volumes are based on a gauged-hole. Adjustments will be made based on caliper.

- A) For Surface casing, if cement falls or does not circulate to surface, cement will be topped off.
- B) Cement will not be placed down annulus with a 1" pipe unless BLM is contacted.
- C) The State of Utah will be notified 24 hours prior to running casing and cementing.

4. PRESSURE CONTROL EQUIPMENT

- A) The State of Utah, Division of Oil, Gas and Mining will be notified 24 hours prior to all BOPE pressure tests.
- B) The BOPE shall be closed whenever the well is unattended.
 - a) All BOPE connections subjected to well pressure will be flanged, welded, or clamped.
 - b) Choke Manifold:

- i) Tee blocks or targeted 'T's will be used and anchored to prevent slip and reduce vibration.
- ii) Two adjustable chokes will be used in the choke manifold.
- iii) All valves (except chokes) in kill line choke manifold and choke line will not restrict the flow.
- iv) Pressure gauges in the well control system will be designed for drilling fluid.

C) BOPE Testing:

- a) BOPE shall be pressure tested when initially installed, whenever any seal subject to pressure testing is broken, or after repairs.
- b) All BOP tests will be performed with a test plug in place.
- c) BOP will be tested to full stack working pressure and annular preventer to 50% stack working pressure.

INTERVAL	BOP EQUIPMENT
0 – 1100 ±	11" Diverter with Rotating Head
1100 ± – TD	3,000# Ram Double BOP & Annular with Diverter & Rotating Head

NOTE: Drilling spool to accommodate choke and kill lines.

5. MUD PROGRAM

- A) Mud test will be performed at least every 24 hours and after mudding up to determine density, viscosity, gel strength, filtration, and pH.
- B) Gas-detecting equipment will be installed and operated in the mud-return system from top of Green River Formation to TD.
 - a) Flare line discharge will be located no less than 100 feet from the wellhead using straight or targeted 'T's and anchors.

INTERVAL	MUD WGHT	VISC	FLUID LOSS	COMMENTS
SURF – 1100 ±	8.4 – 8.7 ppg	32	NC	Spud Mud
1100 ± – TD	8.6 – 9.2 ppg	40	NC	DAP/Gel

NOTE: Mud weight increases will be directed by hole conditions.

6. ABNORMAL CONDITIONS

- A) No abnormal pressures or temperatures are anticipated.
 - a) Estimated bottom hole pressure at TD will be approximately 3,913 psi (normal pressure gradient: 0.433 psi/ft).
 - b) Estimated maximum surface pressure will be approximately 1,988 psi (estimated bottom hole minus pressure of partially evacuated hole (gradient: 0.220 psi/ft)).
- B) No hydrogen sulfide is anticipated.

INTERVAL	CONDITION
SURF – 1100 ±	Lost Circulation Possible
1100 ± – TD	Lost Circulation Possible

7. AUXILIARY EQUIPMENT

- A) Choke Manifold

- B) Upper and lower kelly cock with handle available
- C) Stabbing valve
- D) Safety valve and subs to fit all string connections in use

8. **SURVEY & LOGGING PROGRAMS**

- A) Cores: None anticipated.
- B) Testing: None anticipated.
- C) Directional Drilling: Directional tools will be used to locate the bottom hole per the attached directional plan +/-.
- D) Open Hole Logs: TD to surface casing: resistivity, neutron density, gamma ray and caliper.
- E) Mud Logs: Computerized 2-person logging unit will catch and describe 10 foot samples from top of Green River Formation to TD; record and monitor gas shows and record drill times (normal mud logging duties).

9. **HAZARDOUS MATERIALS**

In accordance with Superfund Amendments and Reauthorization Act of 1986 (SARA) Title III, no chemicals subject to reporting in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well.

T7S, R20E, S.L.B.&M.

AXIA ENERGY


Well location, THREE RIVERS #32-15-720, located as shown in the SW 1/4 SW 1/4 of Section 32, T7S, R20E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK (38EAM) LOCATED IN THE SW 1/4 OF SECTION 9, T7S, R20E, S.L.B.&M. TAKEN FROM THE PELICAN LAKE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4942 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
KAY
REGISTRATION NO. 161319
STATE OF UTAH

05-03-12

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'
DATE SURVEYED: 04-03-12 DATE DRAWN: 04-19-12


PARTY B.H. A.S. R.L.L. REFERENCES G.L.O. PLAT
WEATHER WARM FILE AXIA ENERGY


LEGEND:

- 90° SYMBOL
- PROPOSED WELL HEAD.
- SECTION CORNERS LOCATED

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S89°28'29"W	430.13'

NAD 83 (TARGET BOTTOM HOLE)		NAD 83 (SURFACE LOCATION)	
LATITUDE = 40°09'37.78" (40.160494)	LATITUDE = 40°09'37.82" (40.160506)	LATITUDE = 40°09'37.82" (40.160506)	LATITUDE = 40°09'37.95" (40.160542)
LONGITUDE = 109°42'02.02" (109.700561)	LONGITUDE = 109°41'56.48" (109.699022)	LONGITUDE = 109°41'56.48" (109.699022)	LONGITUDE = 109°41'53.98" (109.698328)
NAD 27 (TARGET BOTTOM HOLE)		NAD 27 (SURFACE LOCATION)	
LATITUDE = 40°09'37.91" (40.160531)	LATITUDE = 40°09'37.95" (40.160542)	LATITUDE = 40°09'37.95" (40.160542)	LATITUDE = 40°09'37.95" (40.160542)
LONGITUDE = 109°41'59.51" (109.699864)	LONGITUDE = 109°41'53.98" (109.698328)	LONGITUDE = 109°41'53.98" (109.698328)	LONGITUDE = 109°41'53.98" (109.698328)





LEGEND:

● PROPOSED LOCATION



AXIA ENERGY

THREE RIVERS #32-15-720 & #32-25-720
SECTION 32, T7S, R20E, S.L.B.&M
SW 1/4 SW 1/4



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

ACCESS ROAD
MAP


04 26 12
MONTH DAY YEAR



SCALE: 1:100,000

DRAWN BY: C.I.

REVISED: 06-26-12

**LEGEND:**

- EXISTING ROAD
- - - - - PROPOSED ACCESS ROAD
- . - . - EXISTING POWER LINE

N**AXIA ENERGY**

THREE RIVERS #32-15-720 & #32-25-720
SECTION 32, T7S, R20E, S.L.B.&M
SW 1/4 SW 1/4



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

ACCESS ROAD
MAP


04 26 12
 MONTH DAY YEAR

SCALE: 1" = 2000'

DRAWN BY: C.I.

REVISED: 06-26-12

B
TOPO



LEGEND:

- ⊘ DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



AXIA ENERGY


THREE RIVERS #32-15-720 & #32-25-720
SECTION 32, T7S, R20E, S.L.B.&M.
SW 1/4 SW 1/4

**TOPOGRAPHIC
MAP**

04 26 12
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.I. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 1,711' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- - - - - PROPOSED PIPELINE
- - - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)



AXIA ENERGY

THREE RIVERS #32-15-720 & #32-25-720
SECTION 32, T7S, R20E, S.L.B.&M.
SW 1/4 SW 1/4



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
MAP**

04 26 12
MONTH DAY YEAR

SCALE: 1" = 2000'

DRAWN BY: C.I.


REVISED: 06-26-12

**D
TOPO**

E
TOPO


Axia Energy

Project: Uintah County, UT
 Site: SEC 32-T7S-R20E
 Well: Three Rivers #32-15-720
 Wellbore: DD
 Design: Plan #1



SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	1000.0	0.00	0.00	1000.0	0.0	0.0	0.00	0.00	0.0	
3	1485.7	9.71	269.42	1483.4	-0.4	-41.1	2.00	269.42	41.1	
4	3548.5	9.71	269.42	3516.6	-3.9	-389.1	0.00	0.00	389.2	
5	4034.2	0.00	0.00	4000.0	-4.4	-430.2	2.00	180.00	430.2	
6	9070.2	0.00	0.00	9036.0	-4.4	-430.2	0.00	0.00	430.2	Three Rivers #32-15-720 PBHL



Azimuths to True North
 Magnetic North: 11.06°
 Magnetic Field
 Strength: 52298.8snT
 Dip Angle: 65.94°
 Date: 5/15/2012
 Model: IGRF2010

FORMATION TOP DETAILS

TVDPPath	MDPath	Formation
3106.0	3131.9	Top Green River
3423.0	3453.5	Top Birds Nest
3893.0	3927.2	Base Birds Nest
4094.0	4128.2	Temperature 120
5123.0	5157.2	Garden Gulch (MGR Marker)
6886.0	6920.2	Top Uteland Butte (LGR Marker)
7036.0	7070.2	Top Wasatch (Base Uteland)

Type	Target	Azimuth	Origin	Type	N/S	E/W	From
Three Rivers #32-15-720 PBHL	Three Rivers #32-15-720 PBHL	269.42	Slot	0.0	0.0	0.0	0.0
TD	9036.0	+N/-S	-4.4	+E/-W	-430.2	Latitude	40.160494
						Longitude	-109.700561

RECEIVED: May 23, 2012

Planning Report

Database:	USA EDM 5000 Multi Users DB	Local Co-ordinate Reference:	Well Three Rivers #32-15-720
Company:	Axia Energy	TVD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Project:	Uintah County, UT	MD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Site:	SEC 32-T7S-R20E	North Reference:	True
Well:	Three Rivers #32-15-720	Survey Calculation Method:	Minimum Curvature
Wellbore:	DD		
Design:	Plan #1		

Project	Uintah County, UT		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Northern Zone		

Site		SEC 32-T7S-R20E			
Site Position:		Northing:	3,224,156.48 ft	Latitude:	40.163383
From:	Lat/Long	Easting:	2,144,775.24 ft	Longitude:	-109.695589
Position Uncertainty:	0.0 ft	Slot Radius:	13.200 in	Grid Convergence:	1.19 °

Well	Three Rivers #32-15-720					
Well Position	+N/-S	0.0 ft	Northing:	3,223,088.57 ft	Latitude:	40.160506
	+E/-W	0.0 ft	Easting:	2,143,837.54 ft	Longitude:	-109.699022
Position Uncertainty		0.0 ft	Wellhead Elevation:	ft	Ground Level:	4,800.0 ft

Wellbore	DD				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2010	5/15/2012	11.06	65.94	52,299

Design	Plan #1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(ft)	(ft)	(ft)	(°)
	0.0	0.0	0.0	269.42

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,485.7	9.71	269.42	1,483.4	-0.4	-41.1	2.00	2.00	0.00	269.42	
3,548.5	9.71	269.42	3,516.6	-3.9	-389.1	0.00	0.00	0.00	0.00	
4,034.2	0.00	0.00	4,000.0	-4.4	-430.2	2.00	-2.00	0.00	180.00	
9,070.2	0.00	0.00	9,036.0	-4.4	-430.2	0.00	0.00	0.00	0.00	Three Rivers #32-15-

Planning Report

Database:	USA EDM 5000 Multi Users DB	Local Co-ordinate Reference:	Well Three Rivers #32-15-720
Company:	Axia Energy	TVD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Project:	Uintah County, UT	MD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Site:	SEC 32-T7S-R20E	North Reference:	True
Well:	Three Rivers #32-15-720	Survey Calculation Method:	Minimum Curvature
Wellbore:	DD		
Design:	Plan #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Comments / Formations
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	KOP @ 1000'
1,100.0	2.00	269.42	1,100.0	0.0	-1.7	1.7	2.00	2.00	
1,200.0	4.00	269.42	1,199.8	-0.1	-7.0	7.0	2.00	2.00	
1,300.0	6.00	269.42	1,299.5	-0.2	-15.7	15.7	2.00	2.00	
1,400.0	8.00	269.42	1,398.7	-0.3	-27.9	27.9	2.00	2.00	
1,485.7	9.71	269.42	1,483.4	-0.4	-41.1	41.1	2.00	2.00	EOB; Inc=9.71°
1,500.0	9.71	269.42	1,497.5	-0.4	-43.5	43.5	0.00	0.00	
1,600.0	9.71	269.42	1,596.0	-0.6	-60.4	60.4	0.00	0.00	
1,700.0	9.71	269.42	1,694.6	-0.8	-77.2	77.2	0.00	0.00	
1,800.0	9.71	269.42	1,793.2	-1.0	-94.1	94.1	0.00	0.00	
1,900.0	9.71	269.42	1,891.7	-1.1	-111.0	111.0	0.00	0.00	
2,000.0	9.71	269.42	1,990.3	-1.3	-127.9	127.9	0.00	0.00	
2,100.0	9.71	269.42	2,088.9	-1.5	-144.7	144.7	0.00	0.00	
2,200.0	9.71	269.42	2,187.4	-1.6	-161.6	161.6	0.00	0.00	
2,300.0	9.71	269.42	2,286.0	-1.8	-178.5	178.5	0.00	0.00	
2,400.0	9.71	269.42	2,384.6	-2.0	-195.3	195.4	0.00	0.00	
2,500.0	9.71	269.42	2,483.1	-2.2	-212.2	212.2	0.00	0.00	
2,600.0	9.71	269.42	2,581.7	-2.3	-229.1	229.1	0.00	0.00	
2,700.0	9.71	269.42	2,680.3	-2.5	-246.0	246.0	0.00	0.00	
2,800.0	9.71	269.42	2,778.8	-2.7	-262.8	262.9	0.00	0.00	
2,900.0	9.71	269.42	2,877.4	-2.8	-279.7	279.7	0.00	0.00	
3,000.0	9.71	269.42	2,976.0	-3.0	-296.6	296.6	0.00	0.00	
3,100.0	9.71	269.42	3,074.5	-3.2	-313.5	313.5	0.00	0.00	
3,131.9	9.71	269.42	3,106.0	-3.2	-318.9	318.9	0.00	0.00	Top Green River
3,200.0	9.71	269.42	3,173.1	-3.3	-330.3	330.4	0.00	0.00	
3,300.0	9.71	269.42	3,271.7	-3.5	-347.2	347.2	0.00	0.00	
3,400.0	9.71	269.42	3,370.2	-3.7	-364.1	364.1	0.00	0.00	
3,453.5	9.71	269.42	3,423.0	-3.8	-373.1	373.1	0.00	0.00	Top Birds Nest
3,500.0	9.71	269.42	3,468.8	-3.9	-381.0	381.0	0.00	0.00	
3,548.5	9.71	269.42	3,516.6	-3.9	-389.1	389.2	0.00	0.00	Start Drop -2.00
3,600.0	8.68	269.42	3,567.4	-4.0	-397.4	397.4	2.00	-2.00	
3,700.0	6.68	269.42	3,666.5	-4.2	-410.7	410.8	2.00	-2.00	
3,800.0	4.68	269.42	3,766.0	-4.3	-420.6	420.7	2.00	-2.00	
3,900.0	2.68	269.42	3,865.8	-4.3	-427.1	427.1	2.00	-2.00	
3,927.2	2.14	269.42	3,893.0	-4.3	-428.2	428.2	2.00	-2.00	Base Birds Nest
4,000.0	0.68	269.42	3,965.8	-4.4	-430.0	430.0	2.00	-2.00	
4,034.2	0.00	0.00	4,000.0	-4.4	-430.2	430.2	2.00	-2.00	EOD; Inc=0°
4,100.0	0.00	0.00	4,065.8	-4.4	-430.2	430.2	0.00	0.00	
4,128.2	0.00	0.00	4,094.0	-4.4	-430.2	430.2	0.00	0.00	Temperature 120
4,200.0	0.00	0.00	4,165.8	-4.4	-430.2	430.2	0.00	0.00	
4,300.0	0.00	0.00	4,265.8	-4.4	-430.2	430.2	0.00	0.00	
4,400.0	0.00	0.00	4,365.8	-4.4	-430.2	430.2	0.00	0.00	

Planning Report

Database: USA EDM 5000 Multi Users DB
Company: Axia Energy
Project: Uintah County, UT
Site: SEC 32-T7S-R20E
Well: Three Rivers #32-15-720
Wellbore: DD
Design: Plan #1

Local Co-ordinate Reference: Well Three Rivers #32-15-720
TVD Reference: KB=16' @ 4816.0ft (Original Well Elev)
MD Reference: KB=16' @ 4816.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Comments / Formations
4,500.0	0.00	0.00	4,465.8	-4.4	-430.2	430.2	0.00	0.00	
4,600.0	0.00	0.00	4,565.8	-4.4	-430.2	430.2	0.00	0.00	
4,700.0	0.00	0.00	4,665.8	-4.4	-430.2	430.2	0.00	0.00	
4,800.0	0.00	0.00	4,765.8	-4.4	-430.2	430.2	0.00	0.00	
4,900.0	0.00	0.00	4,865.8	-4.4	-430.2	430.2	0.00	0.00	
5,000.0	0.00	0.00	4,965.8	-4.4	-430.2	430.2	0.00	0.00	
5,100.0	0.00	0.00	5,065.8	-4.4	-430.2	430.2	0.00	0.00	
5,157.2	0.00	0.00	5,123.0	-4.4	-430.2	430.2	0.00	0.00	Garden Gulch (MGR Marker)
5,200.0	0.00	0.00	5,165.8	-4.4	-430.2	430.2	0.00	0.00	
5,300.0	0.00	0.00	5,265.8	-4.4	-430.2	430.2	0.00	0.00	
5,400.0	0.00	0.00	5,365.8	-4.4	-430.2	430.2	0.00	0.00	
5,500.0	0.00	0.00	5,465.8	-4.4	-430.2	430.2	0.00	0.00	
5,600.0	0.00	0.00	5,565.8	-4.4	-430.2	430.2	0.00	0.00	
5,700.0	0.00	0.00	5,665.8	-4.4	-430.2	430.2	0.00	0.00	
5,800.0	0.00	0.00	5,765.8	-4.4	-430.2	430.2	0.00	0.00	
5,900.0	0.00	0.00	5,865.8	-4.4	-430.2	430.2	0.00	0.00	
6,000.0	0.00	0.00	5,965.8	-4.4	-430.2	430.2	0.00	0.00	
6,100.0	0.00	0.00	6,065.8	-4.4	-430.2	430.2	0.00	0.00	
6,200.0	0.00	0.00	6,165.8	-4.4	-430.2	430.2	0.00	0.00	
6,300.0	0.00	0.00	6,265.8	-4.4	-430.2	430.2	0.00	0.00	
6,400.0	0.00	0.00	6,365.8	-4.4	-430.2	430.2	0.00	0.00	
6,500.0	0.00	0.00	6,465.8	-4.4	-430.2	430.2	0.00	0.00	
6,600.0	0.00	0.00	6,565.8	-4.4	-430.2	430.2	0.00	0.00	
6,700.0	0.00	0.00	6,665.8	-4.4	-430.2	430.2	0.00	0.00	
6,800.0	0.00	0.00	6,765.8	-4.4	-430.2	430.2	0.00	0.00	
6,900.0	0.00	0.00	6,865.8	-4.4	-430.2	430.2	0.00	0.00	
6,920.2	0.00	0.00	6,886.0	-4.4	-430.2	430.2	0.00	0.00	Top Uteland Butte (LGR Marker)
7,000.0	0.00	0.00	6,965.8	-4.4	-430.2	430.2	0.00	0.00	
7,070.2	0.00	0.00	7,036.0	-4.4	-430.2	430.2	0.00	0.00	Top Wasatch (Base Uteland)
7,100.0	0.00	0.00	7,065.8	-4.4	-430.2	430.2	0.00	0.00	
7,200.0	0.00	0.00	7,165.8	-4.4	-430.2	430.2	0.00	0.00	
7,300.0	0.00	0.00	7,265.8	-4.4	-430.2	430.2	0.00	0.00	
7,400.0	0.00	0.00	7,365.8	-4.4	-430.2	430.2	0.00	0.00	
7,500.0	0.00	0.00	7,465.8	-4.4	-430.2	430.2	0.00	0.00	
7,600.0	0.00	0.00	7,565.8	-4.4	-430.2	430.2	0.00	0.00	
7,700.0	0.00	0.00	7,665.8	-4.4	-430.2	430.2	0.00	0.00	
7,800.0	0.00	0.00	7,765.8	-4.4	-430.2	430.2	0.00	0.00	
7,900.0	0.00	0.00	7,865.8	-4.4	-430.2	430.2	0.00	0.00	
8,000.0	0.00	0.00	7,965.8	-4.4	-430.2	430.2	0.00	0.00	
8,100.0	0.00	0.00	8,065.8	-4.4	-430.2	430.2	0.00	0.00	
8,200.0	0.00	0.00	8,165.8	-4.4	-430.2	430.2	0.00	0.00	
8,300.0	0.00	0.00	8,265.8	-4.4	-430.2	430.2	0.00	0.00	
8,400.0	0.00	0.00	8,365.8	-4.4	-430.2	430.2	0.00	0.00	
8,500.0	0.00	0.00	8,465.8	-4.4	-430.2	430.2	0.00	0.00	
8,600.0	0.00	0.00	8,565.8	-4.4	-430.2	430.2	0.00	0.00	
8,700.0	0.00	0.00	8,665.8	-4.4	-430.2	430.2	0.00	0.00	
8,800.0	0.00	0.00	8,765.8	-4.4	-430.2	430.2	0.00	0.00	
8,900.0	0.00	0.00	8,865.8	-4.4	-430.2	430.2	0.00	0.00	
9,000.0	0.00	0.00	8,965.8	-4.4	-430.2	430.2	0.00	0.00	
9,070.2	0.00	0.00	9,036.0	-4.4	-430.2	430.2	0.00	0.00	TD at 9070.2 - Three Rivers #32-15-720 PBHL

Planning Report

Database:	USA EDM 5000 Multi Users DB	Local Co-ordinate Reference:	Well Three Rivers #32-15-720
Company:	Axia Energy	TVD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Project:	Uintah County, UT	MD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Site:	SEC 32-T7S-R20E	North Reference:	True
Well:	Three Rivers #32-15-720	Survey Calculation Method:	Minimum Curvature
Wellbore:	DD		
Design:	Plan #1		

Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)		
Three Rivers #32-15-720 - plan hits target center - Circle (radius 50.0)	0.00	0.00	9,036.0	-4.4	-430.2	3,223,075.29	2,143,407.50	40.160494	-109.700561

Formations						
Measured Depth	Vertical Depth	Name	Lithology	Dip	Dip Direction	
(ft)	(ft)			(°)	(°)	
3,131.9	3,106.0	Top Green River				
3,453.5	3,423.0	Top Birds Nest				
3,927.2	3,893.0	Base Birds Nest				
4,128.2	4,094.0	Temperature 120				
5,157.2	5,123.0	Garden Gulch (MGR Marker)				
6,920.2	6,886.0	Top Uteland Butte (LGR Marker)				
7,070.2	7,036.0	Top Wasatch (Base Uteland)				

Plan Annotations				
Measured Depth	Vertical Depth	Local Coordinates		Comment
(ft)	(ft)	+N/-S (ft)	+E/-W (ft)	
1,000.0	1,000.0	0.0	0.0	KOP @ 1000'
1,485.7	1,483.4	-0.4	-41.1	EOB; Inc=9.71°
3,548.5	3,516.6	-3.9	-389.1	Start Drop -2.00
4,034.2	4,000.0	-4.4	-430.2	EOD; Inc=0°
9,070.2	9,036.0	-4.4	-430.2	TD at 9070.2

Axia Energy

Uintah County, UT

SEC 32-T7S-R20E

Three Rivers #32-15-720

DD

Plan #1

Anticollision Report

15 May, 2012

Anticollision Report

Company:	Axia Energy	Local Co-ordinate Reference:	Well Three Rivers #32-15-720
Project:	Uintah County, UT	TVD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Reference Site:	SEC 32-T7S-R20E	MD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Site Error:	0.0ft	North Reference:	True
Reference Well:	Three Rivers #32-15-720	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0ft	Output errors are at	2.00 sigma
Reference Wellbore	DD	Database:	USA EDM 5000 Multi Users DB
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum

Reference	Plan #1
Filter type:	GLOBAL FILTER APPLIED: All wellpaths within 200'+ 100/1000 of reference
Interpolation Method:	MD Interval 100.0ft
Depth Range:	Unlimited
Results Limited by:	Maximum center-center distance of 1,107.0ft
Warning Levels Evaluated at:	2.00 Sigma
Error Model:	ISCWSA
Scan Method:	Closest Approach 3D
Error Surface:	Elliptical Conic

Survey Tool Program	Date	5/15/2012
From (ft)	To (ft)	Survey (Wellbore)
0.0	9,070.2	Plan #1 (DD)
		Tool Name
		MWD
		Description
		Geolink MWD

Summary						
Site Name	Reference Measured Depth (ft)	Offset Measured Depth (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
SEC 32-T7S-R20E						
Three Rivers #32-25-720 - DD - Plan #1	1,000.0	1,000.0	16.3	12.9	4.745	CC, ES, SF

Anticollision Report

Company:	Axia Energy	Local Co-ordinate Reference:	Well Three Rivers #32-15-720
Project:	Uintah County, UT	TVD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Reference Site:	SEC 32-T7S-R20E	MD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Site Error:	0.0ft	North Reference:	True
Reference Well:	Three Rivers #32-15-720	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0ft	Output errors are at	2.00 sigma
Reference Wellbore	DD	Database:	USA EDM 5000 Multi Users DB
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum

Offset Design SEC 32-T7S-R20E - Three Rivers #32-25-720 - DD - Plan #1														Offset Site Error:	0.0 ft
Survey Program: O-MWD														Offset Well Error:	0.0 ft
Reference		Offset		Semi Major Axis		Distance									
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Total Uncertainty Axis	Separation Factor	Warning		
0.0	0.0	0.0	0.0	0.0	0.0	120.94	-8.4	14.0	16.3						
100.0	100.0	100.0	100.0	0.1	0.1	120.94	-8.4	14.0	16.3	16.0	0.29	55.580			
200.0	200.0	200.0	200.0	0.3	0.3	120.94	-8.4	14.0	16.3	15.7	0.64	25.373			
300.0	300.0	300.0	300.0	0.5	0.5	120.94	-8.4	14.0	16.3	15.3	0.99	16.439			
400.0	400.0	400.0	400.0	0.7	0.7	120.94	-8.4	14.0	16.3	15.0	1.34	12.158			
500.0	500.0	500.0	500.0	0.8	0.8	120.94	-8.4	14.0	16.3	14.6	1.69	9.646			
600.0	600.0	600.0	600.0	1.0	1.0	120.94	-8.4	14.0	16.3	14.3	2.04	7.994			
700.0	700.0	700.0	700.0	1.2	1.2	120.94	-8.4	14.0	16.3	13.9	2.39	6.826			
800.0	800.0	800.0	800.0	1.4	1.4	120.94	-8.4	14.0	16.3	13.6	2.74	5.955			
900.0	900.0	900.0	900.0	1.5	1.5	120.94	-8.4	14.0	16.3	13.2	3.09	5.281			
1,000.0	1,000.0	1,000.0	1,000.0	1.7	1.7	120.94	-8.4	14.0	16.3	12.9	3.43	4.745 CC, ES, SF			
1,100.0	1,100.0	1,099.4	1,099.4	1.9	1.9	-153.89	-8.3	15.7	19.3	15.6	3.78	5.113			
1,200.0	1,199.8	1,198.1	1,197.9	2.1	2.1	-163.01	-8.2	20.8	29.0	24.9	4.12	7.036			
1,300.0	1,299.5	1,295.4	1,294.8	2.3	2.3	-169.38	-8.0	29.2	45.8	41.3	4.46	10.265			
1,400.0	1,398.7	1,390.6	1,389.3	2.5	2.5	-173.07	-7.7	40.5	69.5	64.7	4.79	14.511			
1,500.0	1,497.5	1,483.7	1,481.4	2.7	2.7	-175.24	-7.3	54.6	99.7	94.6	5.11	19.524			
1,600.0	1,596.0	1,578.2	1,574.6	3.0	2.9	-176.53	-6.9	70.0	132.2	126.8	5.44	24.302			
1,700.0	1,694.6	1,672.7	1,667.9	3.3	3.2	-177.31	-6.4	85.3	164.8	159.0	5.78	28.532			
1,800.0	1,793.2	1,767.2	1,761.2	3.6	3.5	-177.84	-6.0	100.6	197.4	191.3	6.11	32.300			
1,900.0	1,891.7	1,861.7	1,854.4	3.9	3.8	-178.21	-5.6	116.0	230.0	223.6	6.45	35.678			
2,000.0	1,990.3	1,956.3	1,947.7	4.2	4.0	-178.49	-5.2	131.3	262.7	255.9	6.78	38.723			
2,100.0	2,088.9	2,050.8	2,041.0	4.5	4.3	-178.71	-4.8	146.6	295.3	288.2	7.12	41.483			
2,200.0	2,187.4	2,145.3	2,134.3	4.9	4.6	-178.89	-4.4	162.0	327.9	320.5	7.45	43.994			
2,300.0	2,286.0	2,239.8	2,227.5	5.2	4.9	-179.04	-3.9	177.3	360.6	352.8	7.79	46.291			
2,400.0	2,384.6	2,334.4	2,320.8	5.5	5.2	-179.16	-3.5	192.6	393.2	385.1	8.12	48.398			
2,500.0	2,483.1	2,428.9	2,414.1	5.8	5.5	-179.26	-3.1	208.0	425.8	417.4	8.46	50.338			
2,600.0	2,581.7	2,523.4	2,507.3	6.2	5.8	-179.34	-2.7	223.3	458.5	449.7	8.79	52.132			
2,700.0	2,680.3	2,617.9	2,600.6	6.5	6.1	-179.42	-2.3	238.6	491.1	482.0	9.13	53.793			
2,800.0	2,778.8	2,712.4	2,693.9	6.8	6.4	-179.49	-1.9	254.0	523.7	514.3	9.46	55.338			
2,900.0	2,877.4	2,807.0	2,787.1	7.2	6.7	-179.55	-1.4	269.3	556.4	546.6	9.80	56.776			
3,000.0	2,976.0	2,901.5	2,880.4	7.5	7.0	-179.60	-1.0	284.6	589.0	578.9	10.13	58.120			
3,100.0	3,074.5	2,996.0	2,973.7	7.8	7.3	-179.64	-0.6	300.0	621.7	611.2	10.47	59.379			
3,200.0	3,173.1	3,090.5	3,066.9	8.2	7.7	-179.69	-0.2	315.3	654.3	643.5	10.80	60.559			
3,300.0	3,271.7	3,185.0	3,160.2	8.5	8.0	-179.72	0.2	330.6	687.0	675.8	11.14	61.668			
3,400.0	3,370.2	3,279.6	3,253.5	8.8	8.3	-179.76	0.6	346.0	719.6	708.1	11.47	62.713			
3,500.0	3,468.8	3,374.1	3,346.7	9.2	8.6	-179.79	1.1	361.3	752.2	740.4	11.81	63.699			
3,600.0	3,567.4	3,468.8	3,440.2	9.5	8.9	-179.82	1.5	376.7	784.4	772.3	12.17	64.473			
3,700.0	3,666.5	3,564.4	3,534.5	9.8	9.2	-179.85	1.9	392.2	813.7	801.2	12.54	64.882			
3,800.0	3,766.0	3,700.6	3,669.4	10.0	9.6	-179.88	2.4	411.1	837.4	824.4	12.98	64.522			
3,900.0	3,865.8	3,840.8	3,809.0	10.2	9.9	-179.90	2.8	423.8	852.8	839.4	13.41	63.581			
4,000.0	3,965.8	3,983.0	3,951.1	10.3	10.1	-179.90	2.9	429.8	860.0	846.1	13.84	62.116			
4,100.0	4,065.8	4,097.7	4,065.8	10.4	10.2	89.51	2.9	430.2	860.5	846.2	14.22	60.509			
4,200.0	4,165.8	4,197.7	4,165.8	10.5	10.4	89.51	2.9	430.2	860.5	845.9	14.57	59.056			
4,300.0	4,265.8	4,297.7	4,265.8	10.7	10.5	89.51	2.9	430.2	860.5	845.5	14.92	57.672			
4,400.0	4,365.8	4,397.7	4,365.8	10.8	10.6	89.51	2.9	430.2	860.5	845.2	15.27	56.351			
4,500.0	4,465.8	4,497.7	4,465.8	10.9	10.7	89.51	2.9	430.2	860.5	844.8	15.62	55.089			
4,600.0	4,565.8	4,597.7	4,565.8	11.0	10.9	89.51	2.9	430.2	860.5	844.5	15.97	53.883			
4,700.0	4,665.8	4,697.7	4,665.8	11.2	11.0	89.51	2.9	430.2	860.5	844.2	16.32	52.728			
4,800.0	4,765.8	4,797.7	4,765.8	11.3	11.1	89.51	2.9	430.2	860.5	843.8	16.67	51.622			
4,900.0	4,865.8	4,897.7	4,865.8	11.4	11.3	89.51	2.9	430.2	860.5	843.5	17.02	50.562			
5,000.0	4,965.8	4,997.7	4,965.8	11.6	11.4	89.51	2.9	430.2	860.5	843.1	17.37	49.544			
5,100.0	5,065.8	5,097.7	5,065.8	11.7	11.5	89.51	2.9	430.2	860.5	842.8	17.72	48.567			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	Axia Energy	Local Co-ordinate Reference:	Well Three Rivers #32-15-720
Project:	Uintah County, UT	TVD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Reference Site:	SEC 32-T7S-R20E	MD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Site Error:	0.0ft	North Reference:	True
Reference Well:	Three Rivers #32-15-720	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0ft	Output errors are at	2.00 sigma
Reference Wellbore	DD	Database:	USA EDM 5000 Multi Users DB
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum


Offset Design SEC 32-T7S-R20E - Three Rivers #32-25-720 - DD - Plan #1													Offset Site Error:	0.0 ft
Survey Program: 0-MWD													Offset Well Error:	0.0 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Total Uncertainty Axis	Separation Factor	Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)						
5,200.0	5,165.8	5,197.7	5,165.8	11.8	11.7	89.51	2.9	430.2	860.5	842.4	18.07	47.627		
5,300.0	5,265.8	5,297.7	5,265.8	12.0	11.8	89.51	2.9	430.2	860.5	842.1	18.42	46.723		
5,400.0	5,365.8	5,397.7	5,365.8	12.1	11.9	89.51	2.9	430.2	860.5	841.7	18.77	45.853		
5,500.0	5,465.8	5,497.7	5,465.8	12.2	12.1	89.51	2.9	430.2	860.5	841.4	19.12	45.014		
5,600.0	5,565.8	5,597.7	5,565.8	12.4	12.2	89.51	2.9	430.2	860.5	841.0	19.46	44.206		
5,700.0	5,665.8	5,697.7	5,665.8	12.5	12.3	89.51	2.9	430.2	860.5	840.7	19.81	43.427		
5,800.0	5,765.8	5,797.7	5,765.8	12.6	12.5	89.51	2.9	430.2	860.5	840.3	20.16	42.674		
5,900.0	5,865.8	5,897.7	5,865.8	12.8	12.6	89.51	2.9	430.2	860.5	840.0	20.51	41.947		
6,000.0	5,965.8	5,997.7	5,965.8	12.9	12.8	89.51	2.9	430.2	860.5	839.6	20.86	41.244		
6,100.0	6,065.8	6,097.7	6,065.8	13.1	12.9	89.51	2.9	430.2	860.5	839.3	21.21	40.565		
6,200.0	6,165.8	6,197.7	6,165.8	13.2	13.1	89.51	2.9	430.2	860.5	838.9	21.56	39.908		
6,300.0	6,265.8	6,297.7	6,265.8	13.4	13.2	89.51	2.9	430.2	860.5	838.6	21.91	39.271		
6,400.0	6,365.8	6,397.7	6,365.8	13.5	13.3	89.51	2.9	430.2	860.5	838.2	22.26	38.655		
6,500.0	6,465.8	6,497.7	6,465.8	13.6	13.5	89.51	2.9	430.2	860.5	837.9	22.61	38.058		
6,600.0	6,565.8	6,597.7	6,565.8	13.8	13.6	89.51	2.9	430.2	860.5	837.5	22.96	37.478		
6,700.0	6,665.8	6,697.7	6,665.8	13.9	13.8	89.51	2.9	430.2	860.5	837.2	23.31	36.917		
6,800.0	6,765.8	6,797.7	6,765.8	14.1	13.9	89.51	2.9	430.2	860.5	836.8	23.66	36.372		
6,900.0	6,865.8	6,897.7	6,865.8	14.2	14.1	89.51	2.9	430.2	860.5	836.5	24.01	35.842		
7,000.0	6,965.8	6,997.7	6,965.8	14.4	14.2	89.51	2.9	430.2	860.5	836.1	24.36	35.328		
7,100.0	7,065.8	7,097.7	7,065.8	14.5	14.4	89.51	2.9	430.2	860.5	835.8	24.71	34.829		
7,200.0	7,165.8	7,197.7	7,165.8	14.7	14.5	89.51	2.9	430.2	860.5	835.4	25.06	34.343		
7,300.0	7,265.8	7,297.7	7,265.8	14.8	14.7	89.51	2.9	430.2	860.5	835.1	25.40	33.871		
7,400.0	7,365.8	7,397.7	7,365.8	15.0	14.8	89.51	2.9	430.2	860.5	834.7	25.75	33.411		
7,500.0	7,465.8	7,497.7	7,465.8	15.1	15.0	89.51	2.9	430.2	860.5	834.4	26.10	32.964		
7,600.0	7,565.8	7,597.7	7,565.8	15.3	15.1	89.51	2.9	430.2	860.5	834.0	26.45	32.529		
7,700.0	7,665.8	7,697.7	7,665.8	15.4	15.3	89.51	2.9	430.2	860.5	833.7	26.80	32.105		
7,800.0	7,765.8	7,797.7	7,765.8	15.6	15.4	89.51	2.9	430.2	860.5	833.3	27.15	31.692		
7,900.0	7,865.8	7,897.7	7,865.8	15.7	15.6	89.51	2.9	430.2	860.5	833.0	27.50	31.290		
8,000.0	7,965.8	7,997.7	7,965.8	15.9	15.8	89.51	2.9	430.2	860.5	832.6	27.85	30.897		
8,100.0	8,065.8	8,097.7	8,065.8	16.0	15.9	89.51	2.9	430.2	860.5	832.3	28.20	30.515		
8,200.0	8,165.8	8,197.7	8,165.8	16.2	16.1	89.51	2.9	430.2	860.5	831.9	28.55	30.141		
8,300.0	8,265.8	8,297.7	8,265.8	16.3	16.2	89.51	2.9	430.2	860.5	831.6	28.90	29.777		
8,400.0	8,365.8	8,397.7	8,365.8	16.5	16.4	89.51	2.9	430.2	860.5	831.2	29.25	29.421		
8,500.0	8,465.8	8,497.7	8,465.8	16.7	16.5	89.51	2.9	430.2	860.5	830.9	29.60	29.074		
8,600.0	8,565.8	8,597.7	8,565.8	16.8	16.7	89.51	2.9	430.2	860.5	830.5	29.94	28.735		
8,700.0	8,665.8	8,697.7	8,665.8	17.0	16.8	89.51	2.9	430.2	860.5	830.2	30.29	28.404		
8,800.0	8,765.8	8,797.7	8,765.8	17.1	17.0	89.51	2.9	430.2	860.5	829.8	30.64	28.080		
8,900.0	8,865.8	8,897.7	8,865.8	17.3	17.2	89.51	2.9	430.2	860.5	829.5	30.99	27.764		
9,000.0	8,965.8	8,997.7	8,965.8	17.4	17.3	89.51	2.9	430.2	860.5	829.1	31.34	27.454		
9,043.8	9,009.6	9,041.5	9,009.6	17.5	17.4	89.51	2.9	430.2	860.5	829.0	31.49	27.321		
9,070.2	9,036.0	9,059.9	9,028.0	17.5	17.4	89.51	2.9	430.2	860.5	828.9	31.57	27.254		

Anticollision Report

Company:	Axia Energy	Local Co-ordinate Reference:	Well Three Rivers #32-15-720
Project:	Uintah County, UT	TVD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Reference Site:	SEC 32-T7S-R20E	MD Reference:	KB=16' @ 4816.0ft (Original Well Elev)
Site Error:	0.0ft	North Reference:	True
Reference Well:	Three Rivers #32-15-720	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0ft	Output errors are at	2.00 sigma
Reference Wellbore	DD	Database:	USA EDM 5000 Multi Users DB
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to KB=16' @ 4816.0ft (Original Well Elev)
Offset Depths are relative to Offset Datum
Central Meridian is -111.500000 °

Coordinates are relative to: Three Rivers #32-15-720
Coordinate System is US State Plane 1983, Utah Northern Zone
Grid Convergence at Surface is: 1.19°



BOP Equipment

3000psi WP




EXHIBIT "F"

AXIA ENERGY

LOCATION LAYOUT FOR

THREE RIVERS #32-15-720 & #32-25-720

SECTION 32, T7S, R20E, S.L.B.&M.


SW1/4 SW1/4

FIGURE #1

SCALE: 1" = 60'

DATE: 04-19-12

DRAWN BY: R.L.L.



Elev. Ungraded Ground At #32-15-720 Loc. Stake = **4800.3'**, UINAH ENGINEERING & LAND SURVEYING
FINISHED GRADE ELEV. AT #32-15-720 LOC. STAKE = **4800.0'**,
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: May 23, 2012

AXIA ENERGY

TYPICAL CROSS SECTIONS FOR

THREE RIVERS #32-15-720 & #32-25-720



SECTION 32, T7S, R20E, S.L.B.&M.

SW1/4 SW1/4


FIGURE #2

X-Section
Scale
1" = 40'
1" = 100'


DATE: 04-19-12
DRAWN BY: R.L.L.




STA. 3+66



STA. 1+70



STA. 0+70



STA. 0+00

NOTE:

Topsoil should not be
Stripped Below Finished
Grade on Substructure Area.

APPROXIMATE ACREAGES

WELL SITE DISTURBANCE = ± 3.570 ACRES
ACCESS ROAD DISTURBANCE = ± 1.154 ACRES
PIPELINE DISTURBANCE = ± 1.161 ACRES
POWERLINE DISTURBANCE = ± 1.142 ACRES
TOTAL = ± 7.027 ACRES

* NOTE:
FILL QUANTITY INCLUDES
5% FOR COMPACTION

APPROXIMATE YARDAGES

(6") Topsoil Stripping = 2,050 Cu. Yds.
Remaining Location = 7,390 Cu. Yds.
TOTAL CUT = 9,440 CU. YDS.
FILL = 1,760 CU. YDS.

EXCESS MATERIAL = 7,680 Cu. Yds.
Topsoil & Pit Backfill = 4,900 Cu. Yds.
(1/2 Pit Vol.)
EXCESS UNBALANCE = 2,780 Cu. Yds.
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: May 23, 2012

AXIA ENERGY

TYPICAL RIG LAYOUT FOR


THREE RIVERS #32-15-720 & #32-25-720
SECTION 32, T7S, R20E, S.L.B.&M.
SW1/4 SW1/4

FIGURE #3


SCALE: 1" = 60'

DATE: 04-19-12


DRAWN BY: R.L.L.




Proposed
Access Road



NOTE:
Flare Pit is to be
located a min. of 100'
from the Well Head.







API Number: 4304752736
Well Name: THREE RIVERS 32-15-720
Township T0.7 . Range R2.0 . Section 32
Meridian: SLBM
Operator: AXIA ENERGY LLC

Map Prepared:
 Map Produced by Diana Mason

Units	Wells Query
STATUS	STATUS
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LOC - New Location
PI OIL	OPS - Operation Suspended
PP GAS	PA - Plugged Abandoned
PP GEOTHERM	PGW - Producing Gas Well
PP OIL	POW - Producing Oil Well
SECONDARY	SGW - Shut-in Gas Well
TERMINATED	SOW - Shut-in Oil Well
	TA - Temp. Abandoned
	TW - Test Well
	WDW - Water Disposal
	WW - Water Injection Well
	WSW - Water Supply Well
Fields	
Unknown	
ABANDONED	
ACTIVE	
COMBINED	
INACTIVE	
STORAGE	
TERMINATED	



Well Name	AXIA ENERGY LLC THREE RIVERS 32-15-720 43047527360000			
String	SURF	PROD		
Casing Size(in)	8.625	5.500		
Setting Depth (TVD)	1100	9036		
Previous Shoe Setting Depth (TVD)	0	1100		
Max Mud Weight (ppg)	8.7	9.2		
BOPE Proposed (psi)	1000	3000		
Casing Internal Yield (psi)	3390	7740		
Operators Max Anticipated Pressure (psi)	3913	8.3		

Calculations	SURF String	8.625	"
Max BHP (psi)	.052*Setting Depth*MW=	498	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	366	YES <input type="checkbox"/> diverter with rotating head
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	256	YES <input type="checkbox"/> OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	256	NO <input type="checkbox"/> OK
Required Casing/BOPE Test Pressure=		1100	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	PROD String	5.500	"
Max BHP (psi)	.052*Setting Depth*MW=	4323	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	3239	NO <input type="checkbox"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2335	YES <input type="checkbox"/> OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	2577	NO <input type="checkbox"/> REasonable
Required Casing/BOPE Test Pressure=		3000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		1100	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO <input type="checkbox"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO <input type="checkbox"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO <input type="checkbox"/>
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO <input type="checkbox"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO <input type="checkbox"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO <input type="checkbox"/>
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

43047527360000 Three Rivers 32-15-720

Casing Schematic



Well name:	43047527360000 Three Rivers 32-15-720	
Operator:	Axia Energy LLC	Project ID:
String type:	Surface	43-047-52736
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.700 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 89 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 115 ft

Burst

Max anticipated surface pressure: 968 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,100 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 958 ft

Directional well information:

Kick-off point 1000 ft
Departure at shoe: 2 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 2 °

Re subsequent strings:

Next setting depth: 9,036 ft
Next mud weight: 9.200 ppg
Next setting BHP: 4,318 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,100 ft
Injection pressure: 1,100 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1100	8.625	32.00	J-55	LT&C	1100	1100	7.875	8864

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	497	2480	4.988	1100	3930	3.57	35.2	417	11.85 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801-538-5357
FAX: 801-359-3940

Date: August 9, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1100 ft, a mud weight of 8.7 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Well name:	43047527360000 Three Rivers 32-15-720		
Operator:	Axia Energy LLC	Project ID:	43-047-52736
String type:	Production		
Location:	UINTAH COUNTY		

Design parameters:**Collapse**

Mud weight: 9.200 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 201 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 3,948 ft

Burst

Max anticipated surface pressure: 2,331 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 4,318 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 7,809 ft

Directional Info - Build & Drop

Kick-off point 1000 ft
Departure at shoe: 430 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 0 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9070	5.5	17.00	N-80	LT&C	9036	9070	4.767	51122
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4318	6290	1.457	4318	7740	1.79	153.6	348	2.27 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: August 9, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9036 ft, a mud weight of 9.2 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.



2580 Creekview Road
Moab, Utah 84532
435/719-2018

August 21, 2012

Mrs. Diana Mason
State of Utah
Division of Oil Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Request for Exception to Spacing – Axia Energy, LLC – **Three Rivers Federal 32-15-720**
Surface Location: 660' FSL & 890' FWL, SW/4 SW/4, Section 32, T7S, R20E,
Target Location: 660' FSL & 460' FWL, SW/4 SW/4, Section 32, T7S, R20E,
SLB&M, Uintah County, Utah

Dear Diana:

Axia Energy, LLC respectfully submits this request for exception to spacing (R649-3-11) based on geology since the well is located less than 460 feet to the drilling unit boundary. Axia Energy, LLC is the only owner and operator within 460 feet of the surface and target location as well as all points along the intended well bore path and are not within 460 feet of any uncommitted tracts or a unit boundary.

Thank you very much for your timely consideration of this application. Please feel free to contact Jess A. Peonio of Axia Energy, LLC at 720-746-5212 or myself should you have any questions or need additional information.

Sincerely,

Don Hamilton
Agent for Axia Energy, LLC

cc: Jess A. Peonio, Axia Energy, LLC

RECEIVED: August 21, 2012

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator	AXIA ENERGY LLC				
Well Name	THREE RIVERS 32-15-720				
API Number	43047527360000	APD No	6052	Field/Unit	WILDCAT
Location: 1/4,1/4	SWSW	Sec	32	Tw	7.0S
		Rng	20.0E		660 FSL 890 FWL
GPS Coord (UTM)	610791	4446383	Surface Owner	Kay Anderson	

Participants

Shane Wentzel (Axia), Brandon Bowthorpe (UELS), John Busch (dirt contractor), Don Hamilton (permit contractor)

Regional/Local Setting & Topography

This proposed well site is approximately 1.5 miles south of Pelican Lake, but the land here slopes south away from the lake and toward the Green River.

Surface Use Plan**Current Surface Use**

Grazing

**New Road
Miles**

0.32

Well Pad

Width 260 **Length** 366

Src Const Material

Onsite

Surface Formation

UNTA

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

Sparse to no grass, sparse vegetation

Soil Type and Characteristics

Sandy clay loam, with scattered gravel on surface

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diversion Required? N

Berm Required? N

Erosion Sedimentation Control Required? N

Paleo Survey Run? N Paleo Potential Observed? N Cultural Survey Run? N Cultural Resources? N

Reserve Pit

Site-Specific Factors

Site Ranking

Distance to Groundwater (feet)
Distance to Surface Water (feet)
Dist. Nearest Municipal Well (ft)
Distance to Other Wells (feet)
Native Soil Type
Fluid Type
Drill Cuttings
Annual Precipitation (inches)
Affected Populations
Presence Nearby Utility Conduits

Final Score

Sensitivity Level

Characteristics / Requirements

Reverve pit should be 195ft by 100ft by 10ft deep. Axia plans to use a 16 mil liner and felt subliner. This appears to be adequate for this site.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? Y

Other Observations / Comments

Richard Powell
Evaluator

7/18/2012
Date / Time

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
6052	43047527360000	LOCKED	OW	P	No
Operator	AXIA ENERGY LLC		Surface Owner-APD	Kay Anderson	
Well Name	THREE RIVERS 32-15-720		Unit		
Field	WILDCAT		Type of Work	DRILL	
Location	SWSW 32 7S 20E S 660 FSL 890 FWL GPS Coord (UTM) 610800E 4446383N				

Geologic Statement of Basis

Axia proposes to set 925 feet of surface pipe, cemented to surface. The depth to the base of the moderately saline water at this location is estimated to be at approximately 1,100 feet. A search of Division of Water Rights records shows 2 water wells within a 10,000 foot radius of the center of Section 32. Both wells are over a mile from the proposed location. Well uses are listed for irrigation, domestic, and stock watering. Depth is listed for only 1 well at 150 feet. Listed wells probably produce from the Uinta Formation. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Surface casing should be extended to cover the base of the moderately saline groundwater or the production casing cement should be brought up to or above the base of the moderately saline ground water in order to isolate it from fresher water uphole.

Brad Hill
APD Evaluator

7/31/2012
Date / Time

Surface Statement of Basis

This proposed well is on fee surface. This is a two well pad shared with the Three Rivers 32-25-720. Surface owner Kay Anderson was contacted and invited to the presite but chose not to attend. Mr. Anderson stated that he was satisfied with the placement of the well and made no requests. Shane Wentzel of Axia stated that a 16 mil liner and felt subliner would be used and this appears to be adequate for the site. Mr. Wentzel also stated that covert green paint color would be used for all tanks and equipment. This appears to be a good site for placement of this well.

Richard Powell
Onsite Evaluator

7/18/2012
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 5/23/2012

API NO. ASSIGNED: 43047527360000

WELL NAME: THREE RIVERS 32-15-720

OPERATOR: AXIA ENERGY LLC (N3765)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: SWSW 32 070S 200E

Permit Tech Review: ☒

SURFACE: 0660 FSL 0890 FWL

Engineering Review: ☒

BOTTOM: 0660 FSL 0460 FWL

Geology Review: ☒

COUNTY: Uintah

LATITUDE: 40.16050

LONGITUDE: -109.69893

UTM SURF EASTINGS: 610800.00

NORTHINGS: 4446383.00

FIELD NAME: WILDCAT

LEASE TYPE: 4 - Fee

LEASE NUMBER: FEE

PROPOSED PRODUCING FORMATION(S): WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: STATE - LPM9046682☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 49-2262 - RNI at Green River☐ RDCC Review:☒ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☒ R649-3-3. Exception☒ Drilling Unit

Board Cause No: R649-3-11

Effective Date:

Siting:

☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations:

- 1 - Exception Location - bhill
- 5 - Statement of Basis - bhill
- 12 - Cement Volume (3) - hmacdonald
- 15 - Directional - dmason
- 23 - Spacing - dmason
- 25 - Surface Casing - hmacdonald

RECEIVED: August 27, 2012



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: THREE RIVERS 32-15-720

API Well Number: 43047527360000

Lease Number: FEE

Surface Owner: FEE (PRIVATE)

Approval Date: 8/27/2012

Issued to:

AXIA ENERGY LLC, 1430 Larimer Ste 400, Denver, CO 80202

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-11. The expected producing formation or pool is the WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an

area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volume for the 5 1/2 production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 2700' MD as indicated in the submitted drilling plan.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

Carol Daniels - RE: Axia Energy - Section 32 Permits - Notice of Spud

From: Cordell Wold <cwold@axiaenergy.com>
To: Cordell Wold <cwold@axiaenergy.com>, Cindy Turner <cturner@axiaenergy.co...
Date: 9/6/2012 8:56 AM
Subject: RE: Axia Energy - Section 32 Permits - Notice of Spud
CC: "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "davidhackford@utah.gov..."

32-35-720; Will be cementing surface casing this afternoon

*TOTAL R20F S 32 -
THREE RIVERS 32-15-720*

32-15-720; will move Pro-Petro this afternoon and be setting surface casing tomorrow afternoon
(09/07/2012)

Thanks,
Cordell Wold
701-570-5540

From: Cordell Wold
Sent: Wednesday, September 05, 2012 7:14 AM
To: Cindy Turner; richardpowell@utah.gov
Cc: caroldaniels@utah.gov; 'davidhackford@utah.gov'
Subject: Axia Energy - Section 32 Permits - Notice of Spud

32-35-720 – will be moving in Pro-Petro and setting surface casing tomorrow (09/06/2012)

32-15-720 – will be setting conductor today

Thanks,
Cordell Wold
701-570-5540

RECEIVED

SEP 06 2012

DIV. OF OIL, GAS & MINING

From: Cindy Turner
Sent: Tuesday, August 28, 2012 3:47 PM
To: richardpowell@utah.gov
Cc: Cordell Wold; caroldaniels@utah.gov
Subject: Axia Energy - Section 32 Permits - Notice of Spud

Richard, the following wells are not set-up to report Notice of Intent to Spud. I sent you an email earlier this week regarding the setting of conductor on the Three Rivers 32-35-720. Following is an update.

32-35-720 – Spud 08-28-12 - setting conductor currently – need to call in a spud notice, but don't have API #

43047527370000

32-15-720 – will be setting conductor next – need to call in a spud notice, but don't have API #

43047527360000

I will get notices submitted in the Utah DOGM website as soon as they are available.

Thanks

Cindy Turner
AXIA ENERGY, LLC
1430 Larimer Street
Suite 400
Denver, CO 80202
Phone: 720-746-5209
Cell: 303-328-8613
cturner@axiaenergy.com

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-15-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0660 FSL 0890 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527360000
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 9/5/2012	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU Pete Martin, Spud Well 09-05-12 @ 08:00 hrs, drill to 100' and set 16" conductor casing. Cement to surface. Rig down Pete Martin. CURRENT STATUS: Wait on Pro-Petro to drill to surface casing TD.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 12, 2012		
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A	DATE 9/6/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-15-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0660 FSL 0890 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527360000
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/28/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> CHANGE PROD CASING FROM 5-1/2" 17.00# N-80 LTC TO 5-1/2" 17.00# J-55 LTC </div> <div style="width: 35%; text-align: right;"> Approved by the Utah Division of Oil, Gas and Mining Date: September 18, 2012 By: <u>Derek Dunt</u> </div> </div>		
NAME (PLEASE PRINT) Cindy Turner		PHONE NUMBER 720 746-5209
SIGNATURE N/A		TITLE Project Manager
DATE 9/18/2012		

Well name:	43047527360000 Three Rivers 32-15-720		
Operator:	Axia Energy LLC		
String type:	Production	Project ID:	43-047-52736
Location:	UINTAH COUNTY		

Design parameters:**Collapse**

Mud weight: 9.200 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 201 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 3,948 ft

Burst

Max anticipated surface pressure: 2,331 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 4,318 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Directional well information:

Kick-off point 1000 ft
Departure at shoe: 430 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 0 °

Tension is based on buoyed weight.

Neutral point: 7,809 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9070	5.5	17.00	J-55	LT&C	9036	9070	4.767	35139

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4318	4910	1.137	4318	5320	1.23	132.2	247	1.87 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: September 18, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9036 ft, a mud weight of 9.2 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-15-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0660 FSL 0890 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527360000
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/28/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. DEPTH CHANGE: FROM 9,070' TMD / 9,036' TVD TO 7,500' TMD / 7,466' TVD Cement Volumes will be adjusted accordingly. The APD approved a WASATCH Completion. However, based on new proposed TD, we will not drill into the WASATCH, therefore request your approve for a GREEN RIVER Completion.		
<div style="text-align: right;"> Approved by the Utah Division of Oil, Gas and Mining Date: September 25, 2012 By: <u><i>Derek Dunt</i></u> </div>		
NAME (PLEASE PRINT) Cindy Turner		PHONE NUMBER 720 746-5209
SIGNATURE N/A		TITLE Project Manager
DATE 9/18/2012		

Well name:	43047527360000 Three Rivers 32-15-720rev	
Operator:	Axia Energy LLC	Project ID:
String type:	Surface	43-047-52736
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.700 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 89 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 115 ft

Burst

Max anticipated surface pressure: 968 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,100 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 956 ft

Directional well information:

Kick-off point 1000 ft
Departure at shoe: 2 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 2 °

Re subsequent strings:

Next setting depth: 9,036 ft
Next mud weight: 9.200 ppg
Next setting BHP: 4,318 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,100 ft
Injection pressure: 1,100 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1100	8.625	24.00	J-55	ST&C	1100	1100	7.972	5662
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	497	1343	2.701 ✓	1100	2950	2.68 ✓	26.4	244	9.24 J ✓

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801-538-5357
FAX: 801-359-3940

Date: September 24, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1100 ft, a mud weight of 8.7 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-15-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0660 FSL 0890 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527360000
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/8/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> CHANGE SURF CASING FROM 8-5/8" 32.00# J-55 LTC TO 8-5/8" 24.00# J-55 STC </div> <div style="width: 35%; text-align: right;"> Approved by the Utah Division of Oil, Gas and Mining Date: September 25, 2012 By: <u>Derek Duff</u> </div> </div>		
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A	DATE 9/18/2012	

Well name:	43047527360000 Three Rivers 32-15-720rev	
Operator:	Axia Energy LLC	Project ID:
String type:	Surface	43-047-52736
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.700 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 89 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 115 ft

Burst

Max anticipated surface pressure: 968 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,100 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 956 ft

Directional well information:

Kick-off point 1000 ft
Departure at shoe: 2 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 2 °

Re subsequent strings:

Next setting depth: 9,036 ft
Next mud weight: 9.200 ppg
Next setting BHP: 4,318 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,100 ft
Injection pressure: 1,100 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1100	8.625	24.00	J-55	ST&C	1100	1100	7.972	5662
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	497	1343	2.701 ✓	1100	2950	2.68 ✓	26.4	244	9.24 J ✓

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801-538-5357
FAX: 801-359-3940

Date: September 24, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1100 ft, a mud weight of 8.7 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

Carol Daniels - Axia Energy, Patterson #51, Production Casing & Cement

From: klbascom <klbascom@ubtanet.com>
To: Carol Daniels <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, ...
Date: 9/22/2012 8:34 PM
Subject: Axia Energy, Patterson #51, Production Casing & Cement

S-32 T 075 R20E

Axia Energy well Three Rivers 32-35-720, API#43-047-52737 reached 7320' td, 9/33/12 @ 03:30. Will run 5.5" production casing & cement late Sunday nite 9/23/12, rig down & move with trucks to Three Rivers 32-15-720, API# 43-047-52736, Monday & rig up Monday 9/24/12. Test BOP Early Tuesday morning. Any questions, contact Kenny Bascom @ 435-828-0697.

Thank You

Kenny Bascom

RECEIVED
SEP 25 2012
DIV. OF OIL, GAS & MINING

Carol Daniels - Fwd: Axia, Patterson #51 Production casing & cement

From: klbascom <klbascom@ubtanet.com>
To: Carol Daniels <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, ...
Date: 10/1/2012 8:56 AM
Subject: Fwd: Axia, Patterson #51 Production casing & cement

T07S R20E S-32 FEE Lease

----- Original Message -----

Subject: Axia, Patterson #51 Production casing & cement
Date: Sun, 30 Sep 2012 20:14:53 -0600
From: klbascom <klbascom@ubtanet.com>
To: Klbascom <klbascom@ubtanet.com>

Axia Energy well Three Rivers 32-15-720, API#43-047-52736 reached 5440' td, 9/29/12 @ 14:30. Will run 5.5" production casing & cement late Monday evening 10/1/12, rig down & move with trucks to Three Rivers 32-41-720, API# 43-047-52876, Tuesday 10/2/12 & rig up. Test BOP Early Wednesday morning. Any questions, contact Kenny Bascom @ 435-828-0697.

Thank You
Kenny Bascom

RECEIVED

OCT 02 2012

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: THREE RIVERS 32-15-720	
2. NAME OF OPERATOR: AXIA ENERGY LLC	9. API NUMBER: 43047527360000	
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202	PHONE NUMBER: 720 746-5200 Ext	9. FIELD and POOL or WILDCAT: WILDCAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0660 FSL 0890 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		COUNTY: UINTAH
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 10/3/2012	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Spud 09-05-12 - Drilled and set 100' 16" conductor casing and cemented to surface. Release spud rig. On 09-08-12 MIRU Pro-Petro and resumed drilling operations. Drilled to 1135' and set 26 jts 8-5/8" 24# J-55 STC @ 1107.07' KB. Cemented with 675 sxs Class "G". Release Pro-Petro Rig. On 09-26-12 MIRU Patterson rig 51 and resumed drilling operations. Drilled to 5,440' TMD / 5,416' TVD. Set 126 jts 5-1/2" 17# J-55 LTC casing @ 5,417.1' KB. Cemented with 350 Sxs Class "G". Patterson Rig 51 released 10-02-12 @ 06:00 hrs. CURRENT STATUS: Wait on Completion.

**Accepted by the
 Utah Division of
 Oil, Gas and Mining
 FOR RECORD ONLY
 October 05, 2012**

NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A		DATE 10/3/2012

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Axia Energy, LLC Operator Account Number: N 3765
Address: 1430 Larimer Street, Suite 400
city Denver,
state CO zip 80202 Phone Number: (720) 746-5209

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304752737	Three Rivers 32-35-720		SESW	32	07S	20E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	<u>new</u>	<u>187166</u>	<u>8/28/2012</u>			<u>10/31/2012</u>	
Comments: APD APPROVED AS WASATCH - SUBMITTED APP TO COMINGLE GREEN RIVER-WASATCH NEED ENTITY NUMBER FOR GR-WS <div style="text-align: right;"> CONFIDENTIAL WSTC BHL: SESW </div>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304752736	Three Rivers 32-15-720		SWSW	32	07S	20E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	<u>new</u>	<u>187167</u>	<u>9/5/2012</u>			<u>10/18/2012</u>	
Comments: APD APPRVD AS WASATCH - DID NOT DRILL INTO WASATCH, SUBMITTED SUNDRY REQUESTING APPROVAL FOR A GREEN RIVER. NEED ENTITY NUMBER FOR GRV <div style="text-align: right;"> CONFIDENTIAL WSTC BHL: SWSW </div>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304752876	Three Rivers 32-41-720		NENE	32	07S	20E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	<u>new</u>	<u>187168</u>	<u>9/12/2012</u>			<u>10/31/2012</u>	
Comments: APD APPRVD AS WASATCH - SUBMITTED APP TO COMINGLE GREEN RIVER WASATCH NEED ENTITY NUMBER FOR GR-WS <div style="text-align: right;"> CONFIDENTIAL WSTC BHL: nene </div>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Cindy Turner

Name (Please Print)

Cindy Turner

Signature

Project Manager

Title

10/2/2012

Date

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-15-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0660 FSL 0890 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527360000
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/13/2012	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 70%;"> Completion Operations Started October 30, 2012 and Ended on November 10, 2012. Completed Formation: Green River (3,353' to 5290') 1st Production: November 6, 2012 1st Sales: November 9, 2012 CURRENT STATUS: On Production </div> <div style="width: 25%; text-align: center;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY December 13, 2012 </div> </div>		
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A	DATE 12/13/2012	

RECEIVED

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

APR 22 2013

AMENDED REPORT ☐
(highlight changes)

FORM 8

DIV. OF OIL, GAS & MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:

FEE

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL:		OIL WELL <input checked="" type="checkbox"/>	GAS WELL <input type="checkbox"/>	DRY <input type="checkbox"/>	OTHER <input type="checkbox"/>	6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
b. TYPE OF WORK:		NEW WELL <input checked="" type="checkbox"/>	HORIZ. LATS. <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	RE-ENTRY <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	OTHER <input type="checkbox"/>
2. NAME OF OPERATOR: AXIA ENERGY, LLC						7. UNIT or CA AGREEMENT NAME	
3. ADDRESS OF OPERATOR: 1430 Larimer St, Ste 400 CITY Denver STATE CO ZIP 80202						8. WELL NAME and NUMBER: THREE RIVERS 32-15-720	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 660' FSL & 890' FWL, S32 T07S R20E AT TOP PRODUCING INTERVAL REPORTED BELOW: 603' FSL 634' FWL, S32 T07S R20E AT TOTAL DEPTH: 569' FSL 578' FWL, S32 T07S R20E						9. API NUMBER: 4304752736	
10. FIELD AND POOL, OR WILDCAT UNDESIGNATED						11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 32 07S 20E	
12. COUNTY UINTAH						13. STATE UTAH	

14. DATE SPURRED: 9/5/2012	15. DATE T.D. REACHED: 9/29/2012	16. DATE COMPLETED: 11/10/2012	ABANDONED <input type="checkbox"/>	READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 4800 GL
18. TOTAL DEPTH: MD 5,440 TVD 5,416	19. PLUG BACK T.D.: MD 5,372 TVD 5,348	20. IF MULTIPLE COMPLETIONS, HOW MANY? * No		21. DEPTH BRIDGE MD PLUG SET: TVD	
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) CBL, MUD LOG, AC-TR-DSN-SD			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input type="checkbox"/> YES <input checked="" type="checkbox"/> (Submit copy)		

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
24	16	75	0	100		G 124	25	0	
12-1/4	8-5/8 J-55	24	0	1,107		G 675	138	0 CALC	
7-3/4	5-1/2 J-55	17	0	5,417		G 350	145	2540' CBL	

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8	4,724							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Green River	3,003	5,440	2,979	5,416	3,353 4,455	.34	111	Open <input type="checkbox"/> Squeezed <input checked="" type="checkbox"/>
(B)					4,485 5,290	.34	93	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
3,353 - 5,290'	Green River Hybrid Frac - 29,547 bbls slurry, 1,182,868 gal fluid & 909,740# 20/40 Premium White.

29. ENCLOSED ATTACHMENTS:

- ☒ ELECTRICAL/MECHANICAL LOGS
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION
☐ GEOLOGIC REPORT
☐ CORE ANALYSIS
☐ DST REPORT
☒ DIRECTIONAL SURVEY
☐ OTHER: _____

30. WELL STATUS:

Prod

CONFIDENTIAL

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 11/6/2012		TEST DATE: 4/13/2013		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL – BBL: 83	GAS – MCF: 137	WATER – BBL: 341	PROD. METHOD: Pumping
CHOKE SIZE: 48	TBG. PRESS. 40	CSG. PRESS. 40	API GRAVITY 25.50	BTU – GAS	GAS/OIL RATIO 1,651	24 HR PRODUCTION RATES: →	OIL – BBL: 83	GAS – MCF: 137	WATER – BBL: 341	INTERVAL STATUS: Open

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Flared

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				Green River Garden Gulch	3,003 4,983

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Cindy TurnerTITLE Project ManagerSIGNATURE Cindy TurnerDATE 4/17-13

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

WELLBORE DIAGRAM (after completion)



Company:	Axia Energy, LLC
Lease Name:	Three Rivers 32-15-720
Surface Location:	SWSW Sec 32-T7S-R20E, 660' FSL & 890' FWL
Bottom Hole Location:	SWSW Sec 32-T7S-R20E, 569' FSL & 578' FWL
County:	Uintah, UT
Date:	4/20/2013

KB 4,817

GL 4,800

DRILLED 22" HOLE TO 100' - SET 16" CONDUCTOR
Cemented with 124 sxs to surface 09-15-12

DRILLED 12-1/4" HOLE TO 880'
SURF CSG - 8-5/8" 24# J-55 ST&C (26 jts) Set 09-08-12
Cement: 675 sxs Class "G" to surface

TOC 2,540'

GREEN RIVER HYBRID FRAC (10-30-12 THRU 11-08-13)			
3353	5290	3 spf	204 Holes
29,547 bbls slurry, 1,182,868 gal fluid, & 909,740# 20/40 Premium White			

CEMENT SQUEEZE WATER ZONE (12-15-12 THRU 03-08-13)				
3353	4455	Squeezed	3 spf	111 Holes
4485	5290	Open	3 spf	93 Holes

DRILLED 7-3/4" HOLE TO ' 5400' TMD
PROD CSG - 5 1/2" 17# J-55 LT&C (117 jts) Set @ 5417' 10-02-12
Cemented with 385 sxs Premium Lite

5417'

TMD 5440
TVD 5416

As Drilled Formation
Tops (MD)

GREEN RIVER 3,003

Production Tubing Set
Set @ 4724'

GARDEN GULCH 4,983

APR 22 2013

DIV. OF OIL, GAS & MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
FEE

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:
THREE RIVERS 32-15-720

9. API NUMBER:
4304752736

10 FIELD AND POOL, OR WILDCAT
UNDESIGNATED

11. QTR/QTR, SECTION, TOWNSHIP, RANGE,
MERIDIAN:
SWSW 32 07S 20E

12. COUNTY UINTAH	13. STATE UTAH
----------------------	-------------------

☒ 17. ELEVATIONS (DF, RKB, RT, GL):
4800 GL

NY? *	21. DEPTH BRIDGE PLUG SET:	MD TVD
-------	-------------------------------	---------------

23.

WAS WELL CORED?	NO <input checked="" type="checkbox"/>	YES <input type="checkbox"/>	(Submit analysis)
WAS DST RUN?	NO <input checked="" type="checkbox"/>	YES <input type="checkbox"/>	(Submit report)
DIRECTIONAL SURVEY?	NO <input type="checkbox"/>	YES <input checked="" type="checkbox"/>	(Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

[illegible]

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8	4,724							

26. PRODUCING INTERVALS

FORMATION NAME					PERFORATION RECORD					
	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)		SIZE	NO. HOLES	PERFORATION STATUS	
(A) Green River	3,003	5,440	2,979	5,416	3,353	4,455	.34	111	Open <input type="checkbox"/>	Squeezed <input checked="" type="checkbox"/>
(B)					4,485	5,290	.34	93	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(C)									Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(D)									Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
3,353 - 5,290'	Green River Hybrid Frac - 29,547 bbls slurry, 1,182,868 gal fluid & 909,740# 20/40 Premium White.

29. ENCLOSED ATTACHMENTS:

☒ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☒ DIRECTIONAL SURVEY
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER:

30. WELL STATUS:

Prod

HALLIBURTON

RECEIVED

APR 22 2013

DIV. OF OIL, GAS & MINING

**AXIA ENERGY LLC
1430 LARIMER ST STE 400
DENVER, Colorado**

Three Rivers 32-15-720

Patterson 51

Post Job Summary Cement Production Casing

Date Prepared: October 17, 2012
Version: 1

Service Supervisor: CARPENTER, LANCE

Submitted by: Charli A Brown

HALLIBURTON

HALLIBURTON

Wellbore Geometry

Job Tubulars					MD		Shoe Joint Length ft
Type	Description	Size in	ID in	Wt lbm/ft	Top ft	Bottom ft	
Casing	8 5/8" Surface Casing	8.63	8.097	24.00	0.00	1,100.00	40.00
Open Hole Section	7 7/8" Open Hole		7.875		1,100.00	5,550.00	0.00
Casing	5 1/2" Production Casing	5.50	4.892	17.00	0.00	5,550.00	40.00

Pumping Schedule

Fluid #	Fluid Type	Fluid Name	Density lbm/gal	Avg Rate bbl/min	Volume
1	Spacer	Fresh Water	8.33	4.00	10.0 bbl
2	Spacer	SUPER FLUSH 101	10.00	4.00	20.0 bbl
3	Spacer	Fresh Water	8.33	4.00	10.0 bbl
4	Cement Slurry	Halliburton Light Premium	12.00	6.00	350.0 sacks
5	Spacer	Clay Web Displacement	8.40	6.00	125.0 bbl

Fluids Pumped

Stage/Plug # 1 **Fluid 1:** Fresh Water
FRESH WATER

Fluid Density: 8.33 lbm/gal
Fluid Volume: 10.00 bbl
Pump Rate: 4.00 bbl/min

Stage/Plug # 1 **Fluid 2:** SUPER FLUSH 101
SUPER FLUSH 101 - SBM (12199)

Fluid Density: 10.00 lbm/gal
Fluid Volume: 20.00 bbl
Pump Rate: 4.00 bbl/min

Stage/Plug # 1 **Fluid 3:** Fresh Water
FRESH WATER

Fluid Density: 8.33 lbm/gal
Fluid Volume: 10.00 bbl
Pump Rate: 4.00 bbl/min

Stage/Plug # 1 **Fluid 4:** Halliburton Light Premium
HALLIBURTON LIGHT PREMIUM - SBM (12311)
0.9 % HR-5
0.125 lbm Poly-E-Flake

Fluid Weight: 12.00 lbm/gal
Slurry Yield: 2.32 ft³/sack
Total Mixing Fluid: 13.09 Gal
Volume: 350.0 sacks
Calculated Fill: 4,100.00 ft
Calculated Top of Fluid: 2,500.00 ft
Pump Rate: 6.00 bbl/min

HALLIBURTON

Stage/Plug # 1 Fluid 5: Clay Web
CLA-WEB WATER Displacement

Fluid Density: 8.40 lbm/gal
Fluid Volume: 125.00 bbl
Pump Rate: 6.00 bbl/min

Job Summary

Job Information

Job Start Date	10/1/2012 10:00:00 PM
Job MD	5,427.0 ft
Job TVD	5,427.0 ft
Height of Plug Container/Swage Above Rig Floor	8.0 ft
Surface Temperature at Time of Job	65 degF
Mud Type	Water Based Mud
Actual Mud Density	10 lbm/gal
Time Circulated before job	1.00 hour(s)
Mud Volume Circulated	390.00 bbl
Rate at Which Well was Circulated	6.500 bbl/min
Mud loss while Circulating	20.00 bbl
Units of Gas Detected While Circulating	300 API Gas Units
Pipe Movement During Hole Circulation	Reciprocated
Time From End Mud Circ. to Job Start	10.00 minute
Pipe Movement During Cementing	None
Calculated Displacement	125.00 bbl
Job Displaced by (rig/halco)	Cement Unit HP Pumps
Annular flow Before Job? (Water/Gas)	Unknown
Annular flow After Job? (Water/Gas)	No
Length of Rat Hole	4.00 ft

Cementing Equipment

Number of Centralizers Used	24
Did Float Equipment Hold?	Yes
Plug set used?	No
Did Plugs Bump?	Yes
Calculated Pressure to Bump Plugs	810.0 psig

HALLIBURTON

Service Supervisor Reports

Job Log

Date/Time	Activity Code	Pump Rate	Volume	Pressure (psig)	Comments
10/01/2012 16:30	Call Out				CREW CALLED OUT
10/01/2012 18:15	Pre-Convoy Safety Meeting				CREW HAS JOURNEY MANAGEMENT SAFETY MEETING
10/01/2012 18:30	Depart from Service Center				CREW DEPARTS FOR LOCATION
10/01/2012 20:00	Arrive At Loc				CREW ARRIVES AT LOCATION
10/01/2012 20:10	Assessment Of Location Safety Meeting				CREW ASSESSES LOCATION FOR HAZARDS AND EQUIPMENT LAYOUT
10/01/2012 20:15	Pre-Rig Up Safety Meeting				CREW HAS PRE RIG UP SAFETY MEETING
10/01/2012 21:00	Casing on Bottom				CASING ON BOTTOM. CASING CREW BEGINS RIGGING DOWN
10/01/2012 21:15	Rig-Up Equipment				CREW BEGINS RIGGING UP EQUIPMENT
10/01/2012 21:40	Pre-Job Safety Meeting				CREW, RIG CREW AND COMPANY REP HAVE PRE JOB SAFETY MEETING
10/01/2012 22:00	Rig-Up Completed				CREW IS RIGGED UP
10/01/2012 22:04	Pump Water	4	10	200.0	PUMP WATER AHEAD
10/01/2012 22:11	Pressure Test				PRESSURE TEST TO 5500 PSI
10/01/2012 22:16	Pump Spacer	4	20	180.0	PUMP 10# SUPERFLUSH
10/01/2012 22:22	Pump Water	4	10	200.0	PUMP WATER BEHIND
10/01/2012 22:28	Pump Cement	6	145	100.0	PUMP CEMENT 12# 2.32 YIELD 13.09 GAL 350 SKS
10/01/2012 22:53	Shutdown				SHUTDOWN
10/01/2012 22:54	Drop Top Plug				DROP LATCHDOWN PLUG PROVIDED BY CUSTOMER
10/01/2012 22:55	Comment				WASH PUMPS AND LINES TO THE PIT
10/01/2012 23:01	Pump Displacement	6	125	850.0	PUMP WATER DISPLACEMENT WITH CLAYWEB
10/01/2012 23:19	Slow Rate				SLOW RATE
10/01/2012 23:23	Bump Plug				BUMP PLUG. TOOK 500 OVER PER CO REP
10/01/2012 23:25	Check Floats				CHECK FLOATS. GOT .75 BBL BACK
10/01/2012 23:30	Post-Job Safety Meeting (Pre Rig-Down)				CREW HAS PRE RIG DOWN SAFETY MEETING

HALLIBURTON

Date/Time	Activity Code	Pump Rate	Volume	Pressure (psig)	Comments
10/01/2012 23:40	Rig-Down Equipment				CREW BEGINS RIGGING DOWN EQUIPMENT
10/02/2012 00:20	Rig-Down Completed				CREW IS RIGGED DOWN
10/02/2012 00:25	Pre-Convoy Safety Meeting				CREW HAS JOURNEY MANAGEMENT SAFETY MEETING
10/02/2012 00:30	Depart Location for Service Center or Other Site				CREW DEPARTS FROM LOCATION

HALLIBURTON

Cementing Job Summary

The Road to Excellence Starts with Safety

Sold To #: 360716		Ship To #: 2953898		Quote #:		Sales Order #: 9854032	
Customer: AXIA ENERGY LLC				Customer Rep: Peonio, Jess			
Well Name: Three Rivers			Well #: 32-15-720		API/UWI #:		
Field:		City (SAP): VERNAL		County/Parish: Uintah		State: Utah	
Contractor: Patterson			Rig/Platform Name/Num: Patterson 51				
Job Purpose: Cement Production Casing							
Well Type: Development Well			Job Type: Cement Production Casing				
Sales Person: SCOTT, KYLE			Srvc Supervisor: CARPENTER, LANCE			MBU ID Emp #: 461737	

Job Personnel

HES Emp Name	Exp Hrs	Emp #	HES Emp Name	Exp Hrs	Emp #	HES Emp Name	Exp Hrs	Emp #
CARPENTER, LANCE S	0.0	461737	CLARK, SHAUN Cameron	0.0	527195	HUNTER, SAMUEL David	0.0	479669
JUTSUM, TIMOTHY	0.0	510127						

Equipment

HES Unit #	Distance-1 way	HES Unit #	Distance-1 way	HES Unit #	Distance-1 way	HES Unit #	Distance-1 way

Job Hours

Date	On Location Hours	Operating Hours	Date	On Location Hours	Operating Hours	Date	On Location Hours	Operating Hours

TOTAL *Total is the sum of each column separately*

Job

Formation Name	Formation Depth (MD)	Top	Bottom	Form Type	Job depth MD	Job Depth TVD	Water Depth	Perforation Depth (MD)	From	To
				BHST	5427. ft	5427. ft				
						8. ft				

Job Times

Date	Time	Time Zone
01 - Oct - 2012	16:30	MST
01 - Oct - 2012	20:00	MST
01 - Oct - 2012	22:00	MST
01 - Oct - 2012	23:30	MST
02 - Oct - 2012	00:30	MST

Well Data

Description	New / Used	Max pressure psig	Size in	ID in	Weight lbm/ft	Thread	Grade	Top MD ft	Bottom MD ft	Top TVD ft	Bottom TVD ft
7 7/8" Open Hole				7.875				1100.	5550.		
5 1/2" Production Casing	Unknown		5.5	4.892	17.			.	5550.		
8 5/8" Surface Casing	Unknown		8.625	8.097	24.			.	1100.		

Tools and Accessories

Type	Size	Qty	Make	Depth	Type	Size	Qty	Make	Depth	Type	Size	Qty	Make
Guide Shoe					Packer					Top Plug			
Float Shoe					Bridge Plug					Bottom Plug			
Float Collar					Retainer					SSR plug set			
Insert Float										Plug Container			
Stage Tool										Centralizers			

Miscellaneous Materials

Gelling Agt	Conc	Surfactant	Conc	Acid Type	Qty	Conc	%
Treatment Fld	Conc	Inhibitor	Conc	Sand Type	Size		Qty

HALLIBURTON


Cementing Job Summary

Fluid Data									
Stage/Plug #: 1									
Fluid #	Stage Type	Fluid Name	Qty	Qty uom	Mixing Density lbm/gal	Yield ft ³ /sk	Mix Fluid Gal/sk	Rate bbl/min	Total Mix Fluid Gal/sk
1	Fresh Water		10.00	bbl	8.33	.0	.0	.0	
2	SUPER FLUSH 101	SUPER FLUSH 101 - SBM (12199)	20.00	bbl	10.	2.11	13.09	.0	
3	Fresh Water		10.00	bbl	8.33	.0	.0	.0	
4	Halliburton Light Premium	HALLIBURTON LIGHT PREMIUM - SBM (12311)	350.0	sacks	12.	2.32	13.09		13.09
4 %		BENTONITE, BULK (100003682)							
0.4 %		ECONOLITE (100001580)							
0.2 %		HALAD(R)-322, 50 LB (100003646)							
3 lbm		SILICALITE - COMPACTED, 50 LB SK (100012223)							
0.9 %		HR-5, 50 LB SK (100005050)							
0.125 lbm		POLY-E-FLAKE (101216940)							
0.2 %		SUPER CBL, 50 LB PAIL (100003668)							
13.09 Gal		FRESH WATER							
5	Clay Web Displacement		125.00	bbl	8.4	.0	.0	.0	
0.3 gal/Mgal		CLA-WEB - TOTE (101985045)							
Calculated Values		Pressures		Volumes					
Displacement		Shut In: Instant		Lost Returns		Cement Slurry		Pad	
Top Of Cement		5 Min		Cement Returns		Actual Displacement		Treatment	
Frac Gradient		15 Min		Spacers		Load and Breakdown		Total Job	
Rates									
Circulating		Mixing		Displacement		Avg. Job			
Cement Left In Pipe	Amount	40 ft	Reason	Shoe Joint					
Frac Ring # 1 @	ID	Frac ring # 2 @	ID	Frac Ring # 3 @	ID	Frac Ring # 4 @	ID		
The Information Stated Herein Is Correct				Customer Representative Signature					

HALLIBURTON

Data Acquisition

AXIA PRODUCTION THREE RIVERS 32-15-720 PATTERSON 51



Global Event Log

3 Pressure Test 22:11:03

Customer: AXIA
Well Description: THREE RIVERS 32-15-720


Job Date: 01-Oct-2012
UWI:

Sales Order #: 9854032

OptiCem v6.4.9
17-Oct-12 09:27

HALLIBURTON

AXIA PRODUCTION THREE RIVERS 32-15-720 PATTERSON 51



Global Event Log

2	Pump Water	22:04:49	3	Pressure Test	22:11:03	4	Pump Spacer 1	22:16:10
5	Pump Spacer 2	22:22:22	6	Pump Lead Cement	22:28:37	7	Shutdown	22:53:40
8	Drop Top Plug	22:54:31	9	Wash Pumps to Pit	22:55:22	10	Pump Displacement	23:01:57
11	Slow Rate	23:19:22	12	Bump Plug	23:23:02	13	Check Floats	23:24:51

Customer: AXIA
Well Description: THREE RIVERS 32-15-720


Job Date: 01-Oct-2012
UWI:

Sales Order #: 9854032

OptiCem v6.4.9
01-Oct-12 23:32

HALLIBURTON

AXIA PRODUCTION THREE RIVERS 32-15-720 PATTERSON 51



Customer: AXIA
Well Description: THREE RIVERS 32-15-720

Job Date: 01-Oct-2012
UWI:

Sales Order #: 9854032

OptiCem v6.4.9
17-Oct-12 09:28

HALLIBURTON

Lab Data

LAB RESULTS - Primary

Cementing Rockies, Vernal

Job Information

Request/Slurry	275409/1	Rig Name	PATTERSON DRILLING/U #51	Date	28/SEP/2012
Submitted By	Craig Dube	Job Type	Production Casing	Bulk Plant	Vernal
Customer	Axia Energy, LLC.	Location	Uinta	Well	Three Rivers 32-15-720

Well Information

Casing/Liner Size	5 1/2"	Depth MD	5500 ft	BHST	140 F
Hole Size	7 7/8"	Depth TVD	5500 ft	BHCT	102 F

Cement Information - Primary Design

Conc	UOM	Cement/Additive	Sample Type	Sample Date	Lot No.	Cement Properties		
100.00	% BWOC	Cement Blend	Bulk	Sep 28, 2012		Slurry Density	12.00	PPG
0.900	% BWOC	HR-5 (PB)	Bulk	Sep 28, 2012	ND12Y- 06S3TH	Slurry Yield	2.31	ft3/sk
0.125	lb/sk	Pol-E-Flake	Bulk	Sep 28, 2012	4/10/201 2	Water Requirement	13	GPS
13.00	gal/sack	Fresh Water	Lab	Mar 08, 2012	3/8/12	Water Source	Fresh Water	

Operation Test Results Request ID 275409/1

Thickening Time, Request Test ID:2971882

Temp (°F)	Pressure (psi)	Reached in (min)	Start BC	30 Bc (hh:mm)	50 Bc (hh:mm)	70 Bc (hh:mm)	100 Bc (hh:mm)
102	3,200	31	13	01:37	02:01	03:07	03:07

Mixability (0 - 5) - 0 is not mixable, Request Test ID:2971884


Mixability rating (0 - 5)

5

HALLIBURTON

VERNAL

Fields	Values	Fields	Values	Events	Results
Project Name	AXIA 275409-1	Job Type		30.00 Bc	01h:37m
Test ID	275409-1	Cement Type	MOUNTAIN G	50.00 Bc	02h:01m
Request ID	8	Cement Weight	Light Weight	60.00 Bc	02h:46m
Tested by	RR	Test Date	09/28/12	70.00 Bc	03h:07m
Customer	AXIA	Test Time	08:10 PM	100.00 Bc	03h:07m
Well No	THREE RIVERS 32-15-720	Temp. Units	degF	200.00 Bc	NaN
Rig	PATTERSON	Pressure Units	PSI	03h:00m	60.81
Casing/Liner Size				06h:00m	NaN



•fann®

Data File O:\HPHT Data Files\Vernal Consistometer #8\AXIA 275409-1.tdms

Comments

RECEIVED

APR 22 2013



Precision

DIV. OF OIL, GAS & MINING

Survey Report

Client	BIGHORN	MWD Operato	O.Sticca
Energy Company	AXIA ENERGY	Rig Name	Patterson 51
Well Name	Three Rivers 32-15-720	Start Date	9/25/2012
Location	Uintah County, UT	End Date	9/29/2012
API/AFE#		pposed Directi	256.64

Survey Number	MD ft	INC °	AZM °	TVD ft	N-S ft	E-W ft	SECT ft	DLS °/100'
TIE IN	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1	1141.00	0.30	246.20	1140.99	-1.21	-2.73	2.94	0.03
2	1173.00	0.10	277.60	1172.99	-1.24	-2.84	3.05	0.69
3	1205.00	0.40	342.70	1204.99	-1.13	-2.90	3.08	1.15
4	1237.00	0.40	326.20	1236.99	-0.93	-2.99	3.13	0.36
5	1269.00	0.40	315.30	1268.99	-0.75	-3.13	3.22	0.24
6	1300.00	1.30	245.90	1299.99	-0.82	-3.53	3.63	3.93
7	1364.00	3.80	248.30	1363.92	-1.90	-6.17	6.44	3.91
8	1427.00	3.90	251.00	1426.78	-3.37	-10.13	10.64	0.33
9	1491.00	4.70	248.60	1490.60	-5.04	-14.63	15.40	1.28
10	1554.00	5.60	247.10	1553.34	-7.17	-19.86	20.98	1.44
11	1618.00	7.60	245.60	1616.92	-10.14	-26.60	28.22	3.14
12	1681.00	7.70	259.00	1679.36	-12.66	-34.53	36.53	2.83
13	1745.00	7.40	268.30	1742.81	-13.60	-42.86	44.85	1.96
14	1808.00	7.40	272.20	1805.28	-13.57	-50.97	52.73	0.80
15	1872.00	9.00	269.50	1868.63	-13.45	-60.10	61.58	2.57
16	1935.00	10.00	266.00	1930.76	-13.88	-70.48	71.78	1.83
17	1999.00	11.20	263.90	1993.67	-14.93	-82.21	83.43	1.97
18	2063.00	11.60	259.10	2056.41	-16.80	-94.70	96.02	1.61
19	2126.00	11.40	260.20	2118.14	-19.06	-107.06	108.57	0.47
20	2189.00	11.20	257.10	2179.92	-21.49	-119.16	120.90	1.01
21	2253.00	11.30	256.90	2242.69	-24.30	-131.32	133.38	0.17
22	2316.00	11.10	260.30	2304.49	-26.72	-143.31	145.61	1.10

23	2380.00	11.10	258.80	2367.30	-28.95	-155.43	157.91	0.45
24	2443.00	11.00	258.90	2429.13	-31.29	-167.28	169.98	0.16
25	2507.00	10.50	254.40	2492.01	-34.03	-178.89	181.91	1.53
26	2570.00	10.40	257.00	2553.96	-36.85	-189.96	193.33	0.77
27	2633.00	10.40	254.80	2615.93	-39.62	-200.98	204.70	0.63
28	2697.00	9.70	252.00	2678.95	-42.80	-211.69	215.85	1.33
29	2760.00	9.30	254.60	2741.08	-45.80	-221.64	226.23	0.93
30	2823.00	8.70	254.80	2803.31	-48.40	-231.15	236.07	0.95
31	2887.00	8.50	252.70	2866.59	-51.07	-240.33	245.63	0.58
32	2950.00	7.30	247.60	2928.99	-53.98	-248.48	254.23	2.20
33	3014.00	6.20	245.70	2992.54	-56.95	-255.39	261.64	1.75
34	3078.00	5.90	246.10	3056.19	-59.71	-261.55	268.27	0.47
35	3140.00	6.10	251.80	3117.85	-62.03	-267.59	274.68	1.01
36	3203.00	5.40	253.70	3180.53	-63.91	-273.61	280.98	1.15
37	3267.00	4.90	241.60	3244.27	-66.05	-278.91	286.62	1.86
38	3330.00	4.90	238.90	3307.04	-68.72	-283.58	291.79	0.37
39	3394.00	5.00	238.80	3370.81	-71.58	-288.31	297.04	0.16
40	3457.00	4.70	246.90	3433.58	-74.01	-293.03	302.20	1.19
41	3520.00	3.00	257.30	3496.44	-75.39	-297.01	306.39	2.91
42	3584.00	3.10	259.20	3560.35	-76.08	-300.35	309.80	0.22
43	3647.00	3.50	218.90	3623.25	-77.90	-303.23	313.02	3.66
44	3711.00	2.80	234.40	3687.15	-80.33	-305.72	316.01	1.71
45	3774.00	1.60	251.20	3750.11	-81.51	-307.81	318.31	2.14
46	3838.00	0.20	352.10	3814.10	-81.68	-308.67	319.19	2.58
47	3901.00	0.40	306.30	3877.10	-81.44	-308.86	319.32	0.47
48	3965.00	1.40	234.90	3941.09	-81.76	-309.68	320.19	2.07
49	4028.00	0.70	226.10	4004.08	-82.47	-310.59	321.24	1.14
50	4092.00	0.60	159.00	4068.08	-83.06	-310.75	321.53	1.13
51	4155.00	0.90	187.20	4131.07	-83.85	-310.69	321.66	0.74
52	4219.00	0.70	286.80	4195.07	-84.24	-311.13	322.18	1.92
53	4282.00	0.60	284.90	4258.06	-84.04	-311.82	322.80	0.16
54	4409.00	1.60	27.00	4385.05	-82.29	-311.66	322.24	1.44
55	4472.00	0.80	29.10	4448.03	-81.13	-311.04	321.37	1.27
56	4535.00	0.10	354.40	4511.03	-80.69	-310.83	321.07	1.14
57	4599.00	0.60	21.10	4575.03	-80.32	-310.72	320.87	0.80
58	4695.00	0.60	202.40	4671.03	-80.31	-310.73	320.88	1.25
59	4790.00	0.10	255.90	4766.02	-80.79	-311.00	321.25	0.58

60	4885.00	0.50	184.00	4861.02	-81.23	-311.11	321.46	0.50
61	4980.00	0.90	172.60	4956.01	-82.38	-311.04	321.66	0.44
62	5075.00	0.50	170.80	5051.01	-83.53	-310.88	321.77	0.42
63	5171.00	1.00	202.70	5147.00	-84.72	-311.14	322.29	0.66
64	5265.00	1.20	173.90	5240.98	-86.45	-311.35	322.90	0.62
65	5360.00	1.10	189.30	5335.96	-88.34	-311.39	323.38	0.34
66	5392.00	1.90	180.40	5367.95	-89.17	-311.44	323.62	2.60
PTB	5440.00	1.90	180.40	5415.93	-90.77	-311.45	324.00	0.00

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-15-720			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0660 FSL 0890 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527360000			
9. FIELD and POOL or WILDCAT: THREE RIVERS		COUNTY: UINTAH			
STATE: UTAH					
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/1/2013 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> NEW CENTRAL TANK FACILITY: Three Rivers CTB 32-7-20-01 See Attached for Proposal and Allocation Diagram </div> <div style="width: 35%; text-align: right;"> Approved by the Utah Division of Oil, Gas and Mining Date: <u>October 08, 2013</u> By: <u><i>Derek Dunt</i></u> </div> </div>					
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager			
SIGNATURE N/A	DATE 9/11/2013				

AXIA THREE RIVERS CENTRAL TANK FACILITY

Axia Energy, LLC submits the following documentation as follow-up to verbal and email approval to commingle certain wells with common interests per attached diagram.

Allocation Proposal:

Each well that comes on will be set-up and plumbed individually with (2) 500 bbl oil tanks and (1) 500 bbl water tank for each producing well.

When production on a well basis exceeds current individual well storage, production would be gauged and an internal run ticket would be generated. The oil would then be shipped to the centralized tank facilities per attached allocation diagram.

Oil Sales from Centralized Storage Facility would be allocated back to the applicable well on a first in-first out basis and quantity would be based on the run ticket generated when the oil is sold to oil purchaser.


Proposed centralized storage facilities are set up by State or Federal lease number, or in the case of Fee wells, by common interest.

Reporting Requirements:


- When oil is transferred to the central tank battery from a well location, the volume will appear on Form 11 (Monthly Disposition Report) as transported volume for the applicable entity location.
- A Form 12 (Transfer of Oil) for the volume going to the CTB will be prepared with any applicable internal run tickets attached.

EFFECTIVE DATE: October 1, 2013

FACILITY: THREE RIVERS CTB 32-7-20-01
DESC: THREE RIVERS WELLS IN SECTION 32 OF TOWNSHIP 75-RNG 20E THAT CAN FLOW TO CENTRAL TANK BATTERY
LEASE: BASED ON COMMON INTEREST/LEASE NO FEE PRIVATE



When well tanks get full and we are unable to sell, we would move the oil to the central facility for storage/sales using an internal run ticket. Sales from the Central Tank Battery would be allocated back to the wells on a first in - first out basis.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-15-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0660 FSL 0890 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527360000
9. FIELD and POOL or WILDCAT: THREE RIVERS		COUNTY: UINTAH
STATE: UTAH		
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 7/1/2013 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </div> </div>	
OTHER: <input type="text" value="Variance Request"/>		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Please see attached document.		
Approved by the Utah Division of Oil, Gas and Mining Date: <u>November 05, 2013</u> By: <u></u>		
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A	DATE 7/3/2013	

Three Rivers #32-15-720

Notice of Intent start: June 1, 2013

Axia Energy, LLC respectfully requests a variance to the 1800 MCF/MO limit of flaring oil production associated gas on the subject well to the next Utah Board of Oil, Gas and Mining Hearing considering the next filing date. Axia Energy has constructed gas gathering infrastructure within the field and the subject well has been tied into the system but is awaiting gas gatherer ROW approval and construction to send the gas to sales. Axia Energy is requesting the variance to the next available Utah Board Hearing so that: a) the well, which is part of a Upper Green River Pilot program, can be fully evaluated for future opportunities in an Upper Green River development plan in the area, b) production rates can be evaluated to properly size production equipment on the subject well and future wells, c) a decline curve can be evaluated for EUR determination and future planning of drill schedule and capital, and d) production will not be curtailed and EUR decreased due to the shut-in and potential damage to the reservoir (analogous projects operated by Axia Energy have shown a production and EUR decrease due to lengthy shut-ins). The last (Sept., '13) monthly flaring volume for the subject well was 2,690 MCF/MO and efforts will be made to minimize flaring by maximizing fuel usage until the hearing.